

**RECORDED
AS RECEIVED**

The document has been recorded and no further action is necessary.

This page has been added for recording purposes to provide space for the necessary Recorder and/or Assessor stamps and/or recording requirements.

IC 36-2-11-16.5 Requirements for instrument or document presented for recording

Sec. 16.5 (a) This section does not apply to the following:

- (1) A judgment, an order, or a writ of a court.
- (2) A will or death certificate.
- (3) A plat.
- (4) A survey.

(b) The county recorder may receive for record an instrument or a document if:


- (1) the instrument or document consists of at least one (1) individual page measuring not more than eight and one-half (8 1/2) inches by fourteen (14) inches that is not permanently bound and is not a continuous form;
- (2) the instrument or document is on white paper of at least twenty (20) pound weight and has clean margins:
 - (A) on the first and last pages of at least two (2) inches on the top and bottom and one-half (1/2) inch on each side; and
 - (B) on each additional page of at least one-half (1/2) inch on the top, bottom, and each side; and
- (3) the instrument or document is typewritten or computer generated in black ink in at least 10-point type.

IC 36-2-11-15 Instruments that may be received for record or filing; name of person or governmental agency that prepared instrument

I affirm under penalties of perjury, that I have taken reasonable care to redact each social security number in this document unless required by law. This instrument is prepared by:

_____ (printed name of individual)

**OPERATIONS AND MAINTENANCE MANUAL
THE RIDGE ON WILLIAMS CREEK**



PROJECT SITE:

**11.63 Acre Residential Development
Marion County, Indianapolis, IN**

PREPARED FOR:

Thomas Kretz
TMK Development, LLC
9335 Forgotten Creek Drive
Indianapolis, IN 46260


PREPARED BY:

V3 Companies *Matt Vogel*
619 North Pennsylvania Street
Indianapolis, IN 46204
317.423.0690

July 7, 2023

Revised February 8, 2024

DocID:20261137
Tx:42138431





Contents

Introduction	3
Preface	3
Purpose	3
Section I: Owner Information	4
Contact Information for Owner	4
Right of Access	4
Section II: Site BMP Features	6
Introduction	6
Dry Detention Area BMP	7
Introduction	7
Stormwater Infrastructure Inspection Schedule	7
Inspections & Maintenance/Remediation	7
Wet Pond BMP	13
Introduction	13
Stormwater Infrastructure Inspection Schedule	13
Inspections & Maintenance/Remediation	13
Hydrodynamic Separator BMP	14
Introduction	14
Stormwater Infrastructure Inspection Schedule	14
Inspections & Maintenance/Remediation	14
Sump & SNOUT BMPs	16
Introduction	16
Stormwater Infrastructure Inspection Schedule	16
Inspections & Maintenance/Remediation	16
Spill Response Plan	16
Section III: Stormwater Infrastructure	18
Introduction	18
Stormwater Structure Maintenance	19
Stormwater Structure Inspection Schedule	19
Inspections & Maintenance/Remediation	19
Stormwater Conveyance Maintenance	20
Stormwater Conveyance Inspection Schedule	20
Inspections & Maintenance/Remediation	20
Spill Response Plan	21



Appendix A – Inspection & Maintenance Checklists

Appendix B – Invasive Species

Appendix C – Ridge at Williams Creek Subdivision Section I Plans and Details



Introduction

Preface

This Operations and Maintenance Manual (O&M) has been prepared based on guidelines published in the City of Indianapolis, Indiana Stormwater Design and Construction Specifications Manual for TMK Development, LLC. (OWNER).

The Ridge on Williams Creek (SITE) is 11.6 acre +/- property, located at 859 W 96TH ST, Indianapolis, Indiana. The main purpose of the stormwater management Best Management Practices (BMPs) on the site, are to ensure water quantity and quality control by reducing peak runoff discharged from the increased impervious nature of residential development.

Before stormwater leaves the SITE, it is treated for both quality and quantity through the implementation of various BMPs discussed throughout this manual. Water quantity is managed through the use of both wet and dry detention areas. Water quality management occurs through but not limited to the aforementioned basins, grassy swales, and native wet tolerant plantings. The locations of the BMPs, cross section of BMP features, and points of discharge for stormwater treated by the BMPs can be found in The Ridge on Williams Creek plans, included as part of this manual in Appendix C.

Purpose

This Operations and Maintenance Manual (O&M) defines requirements for operating, inspecting, and maintaining The Ridge on Williams Creek infrastructure, including all the BMPs constructed as part of the stormwater plan prepared by V3 Companies (ENGINEER) on behalf of the OWNER. The proposed BMPs intend to provide natural and sustainable water quality and quantity treatment. The OWNER will be responsible for all maintenance and costs associated with routine inspections and maintenance of the integrated stormwater management system BMPs. Brief descriptions of what each BMP is intended to accomplish and the physical processes which govern its behavior are included within the following manual. Inspection and maintenance guidelines specified in this manual should be implemented in order to ensure that BMPs achieve their full performance capabilities.



Section I: Owner Information

Contact Information for Owner

TMK Development, LLC
9335 Forgotten Creek Drive
Indianapolis, IN 46260
Office: 219.878.3918
Contact: Thomas Kretz
tmkretz@gmail.com

- The OWNER is responsible for all maintenance activities and costs associated with said activities within the BMPs.
- The OWNER will keep logs and records of inspections and maintenance activities.
- The OWNER will self-certify when requested by the City that inspections and maintenance was performed according to the O&M Manual.
- The OWNER owner will remove and replace filter media as need, determined by infiltration rate, drain down time, percolation test, etc.

Right of Access

The OWNER hereby grants right of access to the City of Indianapolis to inspect and maintain the BMPs and all other aspects covered within this manual.



Owner Acknowledgement Agreement (“Agreement”)

For good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the undersigned owner (OWNER) hereby submits this Operation and Maintenance Manual (MANUAL) to the City of Indianapolis, Indiana (CITY) as written acknowledgement of Owner’s warranty and agreement to institute, maintain, and follow the water quality Best Management Practices (BMPs) as described in this manual, and to follow and abide by the inspection schedule and maintenance activities listed in this manual. The Owner also hereby agrees to provide, at Owner’s cost, all additional maintenance, repair and/or replacement services reasonably necessary to maintain the function and longevity of the BMPs from and including the date this Agreement is executed by Owner to and including the date on which a new Agreement is filed with the City by another party who assumes all of the obligations and responsibilities of Owner as set forth herein.

Thomas M. Kretz

Owner Signature

3/13/2024

Date

Thomas M. Kretz

Printed Name

TMK Development, LLC.

Company

STATE OF Indiana)

COUNTY OF Marion)

SS:

BEFORE ME, the undersigned a Notary Public in and for said County and State, personally appeared Thomas M. Kretz, Owner, subscribed and sworn before this 13 day of March, 2024.

Marion
County of Residence

02/08/2032
Commission Expiration Date

[Signature]
Signature

Emma Eldridge
Notary Public - Seal
State of Indiana
Marion County
My Commission Expires 02/08/2032
Commission No. NP0754458

Emma Eldridge
Printed Name



Section II: Site BMP Features

Introduction

This section defines responsibilities for operating, inspecting, and maintaining the integrated detention and water quality systems within The Ridge on Williams Creek Subdivision in Indianapolis, Indiana. The subsequent sub-sections below describe in detail what to observe and if deficiencies are found, how to maintain or remediate. This project utilizes BMPs including wet and dry detention areas. In this instance, BMP refers to both water quality and quantity treatment. The operation, inspection, and maintenance of these BMPs are covered in this section. To ensure long-lasting performance, outside of routine landscaping operations for the project, inspections will be the responsibility of the OWNER. Sample inspection and maintenance checklists are included in Appendix A to evaluate each area of concern. Each inspection report shall be kept on file as a permanent record by the OWNER.





Dry Detention Area BMP

Introduction

This type of BMP is considered a natural green infrastructure practice that affords benefits to the environment and receiving infrastructure through transpiration, evaporation, nutrient uptake, floatables and sediment control, as well as carbon sequestration. Strategically placed as part of this project, this type of BMP integrates stormwater runoff conveyance with quantity control and full quality control. Generally, runoff enters the BMP via stormwater infrastructure. The BMP temporarily detains the collected stormwater, where it is filtered through native vegetation. The water is released over time to reduce the total volume sent to storm sewers after a rain event, which helps to reduce flooding. Additionally, this type of BMP provides natural habitats to support wildlife and native plants.

Stormwater Infrastructure Inspection Schedule

The City of Indianapolis will have the right to enter the premises to perform compliance inspections and maintenance of all infrastructure associated with this type of BMP. This BMP's infrastructure components are considered to be the following:

- Inlet/Outlet Pipes, Outlet Control, & Other Structures
- Embankments & Spillway
- Scour Protection Material
- Native Prairie Management
- BMP Surface

Inspections & Maintenance/Remediation

The following are areas critical for inspection to ensure proper working function of the BMP as well as verify optimal treatment performance.

Inlet/Outlet Pipes, Outlet Control, & Other Structures (At Least Quarterly, As Needed)

Inspection

- Visually inspect pipes and structures for damage, displacement, and blockage or restricted stormwater flow by any detritus, sediment, or plant material at least four times per year and following rain events in excess of one (1) inch.

Maintenance

- Remove all debris, trash, floatables, or other material restricting stormwater flow and dispose of properly. Sediment should be removed when the basin is completely dry. Disturbed areas need to be immediately stabilized and re-vegetated with appropriate species.

Remediation

- Repair and/or replace any damaged pipes or structures to their originally designed condition and elevation.

Embankments & Spillway (At Least Biannually, As Needed)

Inspection



Check the slopes of the BMP for erosion or scour protection displacement. Please note the location and describe the failure as specifically as possible. Inspect for evidence of burrowing or tunneling mammals at least twice during the growing season.

Maintenance

- Remove all debris and trash accumulation.

Remediation

- Areas of severe erosion or other conditions that affect the integrity of the BMP or constitute a public safety hazard should be corrected as soon as possible and prior to the next monthly inspection. Burrowing mammals should be controlled or eradicated when they endanger the integrity of the embankments or pose a public safety hazard. Damage caused by their actions must be repaired as soon as possible. Any burrowing mammal control effort will need to be carefully planned and executed to avoid negative impacts on adjacent habitats and wildlife and should be confined to the embankments.

Scour Protection Material (At Least Quarterly, As Needed)

Inspection

- Pay close attention for scour along the edges of the stone material adjacent to the stormwater structures. This indicates the stone is not acting like a channel and instead forcing runoff to the unprotected edges. This can be caused by debris accumulation, washed away stone or insufficient width to adequately convey runoff influent from the outlets to the BMP surface.

Maintenance

- Remove any debris accumulation. Restore any washed away stone from accumulated piles to areas bare from movement.

Remediation

- Should inspection warrant, remediate insufficient stone quantity with similar material to either widen or lengthen the stone section or restore bare areas where stone is missing. Should the remediation be necessary due to insufficient protection, explore options to enhance protection or lessen erosive velocities.

Native Prairie Management (As Identified Below)

All topics covered in Native Prairie Management apply to prairies within identified BMPs, as well as all other prairie areas.

Inspection (Within 1-Year Establishment Period - Monthly)

- Immediately after installation of material and for a minimum of one (1) subsequent year, visual inspection of plant establishment shall be monthly. Depending on planting type, pay close attention to bare areas where seed washed away before establishment. Seed material will take longer to establish than plugs/gallon stock material and may require a longer term of monthly inspections. Additionally, inspect plantings for signs of invasive species. Refer to the Invasive Species appendix of this Manual for common types. Refer to the Performance Standards and Vegetation Monitoring sub-sections below for more detailed information.



Maintenance (Within 1-Year Establishment Period)

- Remove all invasive species found within planted areas. As the native culture establishes over time, the introduction of invasive species will be minimized. Areas where seed has been washed away, re-seed with similar mix. Replace all plant material as needed to prevent erosion. Should inspection warrant, during drought periods, water plantings to continue full establishment and healthy growth.

Inspection (After Establishment Period - Biannually)

- Continue monitoring plant material at a minimum of two (2) times annually. Pay close attention to signs of invasive species. Refer to the Performance Standards and Vegetation Monitoring sub-sections below for more detailed information.

Maintenance (After Establishment Period)

- Remove all invasive species found within planted areas. This activity can coincide with normal landscape maintenance scope of the project. Should inspection warrant, during drought periods, water plantings to continue full establishment and healthy growth. No fertilizer is to be used on this project unless soil testing has found specific deficiencies in nutrients.

Weeding & Herbicide Guidance

- Hand removal or equipment removal of invasive species is preferable to the greatest practical extent (larger planting areas may not be practical). Care should be taken during hand removal, especially within the first year of prairie establishment. Prairie seedlings are delicate and can be pulled up with the weeds. Also, be careful not to mistake prairie plants for weeds. If maintenance staff can identify perennial weeds from annual weeds, perennial weeds should be the focus for hand removal, otherwise, follow the Mowing Guidance sub-section below.
- Within the second year of establishment, annual weeds may still be prevalent, along with common biennial weeds, such as Queen Anne's Lace, Sweet Clover, Wild Parsnip, and Burdock. The Invasive Species Appendix provides a few examples of common invasive species, as well as a link to an exhaustive list found within Indiana.
- Within the third and fourth year of prairie establishment, if perennial weeds appear, they must be controlled immediately, or they may become established and increasingly difficult to manage.
- Controlled spot herbicide applications to manage invasive species are acceptable if warranted and can be done without damaging off-target vegetation. The following provides guidance for applications.
 - Herbicide applications shall be conducted on minimally windy days to ensure chemical does not spread or volatilize. Re-seed and/or replant any die-back resulting from treatment. In all cases, herbicides must be applied using applicators approved by the State Chemist's Office. All herbicide treatment shall be approved by the City of Indianapolis Stormwater Department prior to application.
 - Throughout the first year of establishment, weeds, non-native, or invasive species can be treated with selective herbicide applications approved for use around water (Rodeo) by spot-spraying or other means that minimizes incidental drift. A determination regarding the type of herbicide to be used should be made when it is known which nuisance species are present on the site. Depending on the target weed species, a selective herbicide may be available. The choice of herbicide and timing of herbicide application will be



made by a trained, experienced professional based on the target weed species and conditions. Care should be taken to monitor site weather conditions to limit herbicide drift, overspray, and ensure it is rainfast.

- It is recommended that a minimum of four annual weed control application periods are conducted throughout a three-year management period. Below is a general guideline on the suggested schedule and target species for the application periods:
 1. Application Period One (early spring – April/May): problematic species such as, but not limited to, reed canary grass, red/white clover, cool season adventive grasses.
 2. Application Period Two (late spring to early summer – May/June): problematic species such as, but not limited to, teasel, white/yellow sweet clover, thistle.
 3. Application Period Three (mid to late summer – July/August): problematic species such as, but not limited to, tall goldenrod, hairy aster, ragweed, cattails, purple loosestrife.
 4. Application Period Four (late summer and fall – September/October): problematic species such as, but not limited to, reed canary grass, thistle, common reed, red/white clover, cool season grasses.

Native Prairie Mowing Guidance

- Within the first year of prairie establishment, controlling weeds is critical and should be done with care. Within this period, the prairie should be carefully mowed routinely to a height between four (4) to six (6) inches when weeds reach 12 to 18 inches tall. Do not let plant material get taller than 18 inches, as the subsequent mowing could leave enough material to suppress the growth of prairie seedlings. To greatest extent possible, wait until prairie plant material and underlying soil is dry before it is mown. Never mow wet or soggy plant material. Flail-type mowers are recommended for larger areas because they shred the herbaceous material and pose less risk of injury to the operator from flying debris. Selective weed whipping can be used instead of a mower if conditions are unfit (e.g., too wet or no access) for a tractor, or if only small, isolated areas require cutting.
- Within the second year of prairie establishment, mow the prairie down to roughly 12 inches tall when biennial weeds are in full bloom, but before they set seed, typically around mid to late June. Two mowings may be required at a height of 12 inches in year two, when weeds are in flower but have not yet seeded.
- At the beginning of the third growing season, around mid-Spring, mow the prairie close to the ground. To the greatest practical extent, mown material should be removed to expose the soil to the warming sun. This will encourage the growth of prairie plants over weeds.
- Upon successful establishment, mowing shall be completed once a year in the late spring. Mowing to occur no earlier than May 15th and no later than June 15th. The vegetation should be cut to a height of 6 to 9 inches at this time. Biennial weeds may appear in the third or fourth year, due to dormant seeds surviving in the soil. These weeds will need to be managed on a case-by-case basis, either being pulled or mowed back before they set seed.

Performance Standards

- The three-year management program with specifically identified performance standards



should be conducted for the native prairie establishment so that the relative success may be evaluated. Controlling invasive species is essential to the prairie establishment and will be required to achieve the performance standards for the project. If the performance standards are not achieved by the end of the three-year management program, the OWNER is responsible for correction of any deficiencies through further management activities, which may include replanting. The performance standards are as follows.

- Within 3 months of seed installation, at least 90% of the native prairie, as measured by aerial coverage, shall be vegetated. A minimum 90% vegetative coverage shall be maintained throughout, and at the end of, the three-year period for this area.
- At the end of the first year of the monitoring period, all vegetated areas shall achieve a minimum 10% native vegetative coverage. None of the three most dominant species can be non-native and/or invasive.
- At the end of the second year of the monitoring period, all vegetated areas shall achieve a minimum 25% native vegetative coverage. None of the three most dominant species can be non-native and/or invasive.
- At the end of the third year of the monitoring period, all vegetated areas shall achieve a minimum 75% native vegetative coverage. None of the three most dominant species can be non-native and/or invasive.
- At the end of the third year of the monitoring period the site as a whole shall achieve a Floristic Quality Index of 20 or greater.
- Relative coverage (determined by ocular estimation) of cattails shall be less than 10% throughout, and at the end of, the three-year period.
- Relative coverage (determined by ocular estimation) of common reed, reed canary grass and purple loosestrife in aggregate shall be less than 5% throughout, and at the end of, the three-year period.
- Relative coverage (determined by ocular estimation) of thistle and teasel in aggregate shall be less than 5% throughout, and at the end of, the three-year period.

Vegetation Monitoring

- Annual vegetation monitoring in the native prairie areas will be conducted during the three-year period beginning immediately following planting. Ocular estimation will be used to collect approximate vegetative and species coverage data. The vegetation monitoring inspections will be conducted twice per year in May/June and August/September. In addition, an inventory of all plant species present in these areas should be collected and used to determine desired native species presence.

BMP Surface (At Least Quarterly, As Needed)

Inspection

- Visually inspect the surface of the BMP for indications of excessive ponding due to improper drainage or infiltration. Signs include plant die-off, pockets of shallow pooling, and/or presence of algae pockets. Any ponding at the surface of the BMP for periods



longer than 48-hours is considered a failure and will require maintenance/remediation.

Maintenance

- Scarify top surface soil layers in areas with dead or missing plant material to free up surface voids and break up potential compaction. Remove any dead plant material. Replace soil to originally designed grade, then replant disturbed areas with similar species. Any mulch used to protect seeding should be finished (aged) leaf compost mulch. mulch in areas where depth is less than 2-inches using finished (aged) leaf compost mulch.

Remediation

- Should inspection warrant, BMP soil shall be removed and replaced with modified soil in conformance with design specifications. If the design specifications for the modified soil are deemed inadequate, increase the sand content to increase the permeability of the soil. Pay close attention to minimum organic and topsoil percentages as well as pH levels for plant health.



Wet Pond BMP

Introduction

This type of BMP is considered a practice that affords benefits to the environment and receiving infrastructure through evaporation, floatables, and sediment control. As part of this project, this type of BMP integrates full quality control. Generally, runoff enters the BMP via natural sheet flow. The BMP retains the collected stormwater, where it only leaves the pond when the level reaches the elevation of the outlet pipe. This gives and accumulated sediment to settle to the bottom of the pond and keep from entering the natural Creek downstream. This type of BMP also provides natural habitats to support wildlife.

Stormwater Infrastructure Inspection Schedule

The City of Indianapolis will have the right to enter the premises to perform compliance inspections and maintenance of all infrastructure associated with this type of BMP. This BMP's infrastructure components are considered to be the following:

- Inlet/Outlet Pipes

Inspections & Maintenance/Remediation

The following are areas critical for inspection to ensure proper working function of the BMP as well as verify optimal treatment performance.

Inlet/Outlet Pipes (At Least Quarterly, As Needed)

Inspection

- Visually inspect pipes and structures for damage, displacement, and blockage or restricted stormwater flow by any detritus, sediment, or plant material at least four times per year and following rain events in excess of one (1) inch.

Maintenance

- Remove all debris, trash, floatables, or other material restricting stormwater flow and dispose of properly. Disturbed areas need to be immediately stabilized and re-vegetated with appropriate species.

Remediation

- Repair and/or replace any damaged pipes or structures to their originally designed condition and elevation.



Hydrodynamic Separator BMP

Introduction

This type of BMP is considered a mechanical flow-through practice that affords benefits to the environment and receiving infrastructure through floatables and sediment control. Strategically placed as part of this project, this type of BMP integrates full quality control for the entire site by removal of all total suspended solids. Generally, runoff enters the BMP via stormwater infrastructure. The BMP creates a vortex which is designed to removal total suspended solids, collecting them in a convenient location to be removed completely from the system. The water is released without further restriction compared to the designed release rate and can be installed in-line of other proposed storm sewer infrastructure.

Stormwater Infrastructure Inspection Schedule

The City of Indianapolis will have the right to enter the premises to perform compliance inspections and maintenance of all infrastructure associated with this type of BMP. This BMP's infrastructure components are considered to be the following:

- Inlet/Outlet Pipes & Structures
- Hydrodynamic Separator Manhole Structure

Inspections & Maintenance/Remediation

The following are areas critical for inspection to ensure proper working function of the BMP as well as verify optimal treatment performance.

Inlet/Outlet Pipes & Structures (Annually, As Needed)

Inspection

- Visually inspect pipes and structures for damage, displacement, and blockage or restricted stormwater flow by any debris, sediment, or plant material at least one time per year especially immediately after construction is complete.

Maintenance

- Remove all debris, trash, floatables, or other material restricting stormwater flow and dispose of properly. Sediment should be removed when the upstream basin is completely dry. Surrounding disturbed areas need to be immediately stabilized and re-vegetated with appropriate species.

Remediation

- Repair and/or replace any damaged pipes or structures to their originally designed condition and elevation.

Hydrodynamic Separator Manhole Structure (Annually, As Needed)

Inspection

- Visually inspect inside the structure for damage, displacement, and blockage or restricted stormwater flow by any debris, sediment, or plant material at least one time per year especially immediately after construction is complete.

Maintenance



- Remove all debris, trash, floatables, or other material restricting stormwater flow and dispose of properly. Sediment should be removed when the upstream basin is completely dry. Surrounding disturbed areas need to be immediately stabilized and re-vegetated with appropriate species.

Remediation

- Repair and/or replace any damaged components of the structure to their originally designed condition.



Sump & SNOUT BMPs

Introduction

This document defines responsibilities for operating, inspecting, and maintaining the sump and SNOUT BMPs within the project. The sumps and SNOUTs serve as outlet protection for stormwater from the site. The SNOUTs cover outlet pipes leaving sump structures to collect floatable debris.

Stormwater Infrastructure Inspection Schedule

The City of Indianapolis will have the right to enter the premises to perform compliance inspections and maintenance of all infrastructure associated with this type of BMP. This BMP's infrastructure components are considered to be the following:

- Inlet/Outlet Pipes & Structures

Inspections & Maintenance/Remediation

The following are areas critical for inspection to ensure proper working function of the BMP as well as verify optimal treatment performance.

Inlet/Outlet Pipes & Structures (At Least Quarterly, As Needed)

Inspection

- Visually inspect pipes and structures for damage, displacement, and blockage or restricted stormwater flow by any detritus, sediment, or plant material at least four times per year and following rain events in excess of one (1) inch.

Maintenance

- Remove all debris, trash, floatables, or other material restricting stormwater flow and dispose of properly. Note visible pollution such as oily sheens, discoloration, and cloudy or muddy water. Remove and clean SNOUT upon visual identification of excess hydrocarbons and oils. Sediment removal may be necessary within the sumped areas. Sediment removal is to be accomplished utilizing smaller equipment no larger than a vacuum truck or similar. Any sediment removed shall be placed in a location and removed in a timely manner such that it will not re-enter the system.

Remediation

- Repair and/or replace a damaged SNOUT if necessary.

Spill Response Plan

The proposed land use will consist of single-family residential houses. The pollutants and sources of each pollutant normally expected from this type of land use are listed below:

- Pollutant Source: Passenger vehicles, delivery vehicles, and trucks
 - Type of Pollutant: Oil, gasoline, diesel fuel, any hydrocarbon associated with vehicular fuels and lubricants, grease, antifreeze, windshield cleaner solution, brake fluid, brake dust, rubber, glass, metal and plastic fragments, grit, road de-icing materials
- Pollutant Source: Residence



- Type of Pollutant: Cleaning solutions or solvents, leaks from HVAC equipment, grit from roof drainage, aggregate or rubber fragments from roofing system
- Pollutant Source: Roadway
 - Type of Pollutant: Any pollutant associated with vehicular sources, grit from asphalt wearing surface, bituminous compounds from periodic maintenance (sealing, resurfacing, and patching), pavement de-icing materials, wind-blown litter from off-site sources, and elevated water temperatures from contact with impervious surfaces
- Pollutant Source: Lawn and landscape areas
 - Type of Pollutant: Fertilizers, herbicides, organic material (leaves, mulch, grass clippings) and pesticides.

In case of spill, contact the City of Indianapolis Fire Department (317-736-3650), City of Indianapolis Department of Public Works (888-736-3640), and the IDEM Spill Hotline (317-233-7745).

Responsible Parties

The following owner information is responsible for funding and maintenance of the BMP's listed in the manual:


Owner's Name: TMK Development, LLC
Owner's Address: 9335 Forgotten Creek Drive
Indianapolis, IN 46260



Section III: Stormwater Infrastructure

Introduction

This section defines responsibilities for operating, inspecting, and maintaining the stormwater infrastructure structures and conveyances within The Ridge on Williams Creek Subdivision in Indianapolis, Indiana. The subsequent sub-sections below describe in detail what to observe and if deficiencies are found, how to maintain or remediate. It is critical for the long-term success of stormwater operations to conduct thorough and regular inspections and maintenance of this infrastructure, both part of and separate from the BMPs. Maintenance responsibilities shall remain in effect for the life of the infrastructure from the date the construction is completed. Sample inspection and maintenance checklists are included in Appendix B to evaluate each area of concern, relative to stormwater infrastructure. Each inspection and maintenance checklist shall be kept on file as a permanent record by the OWNER and made available to the City of Indianapolis upon request. Additional inspections are recommended following a significant rainfall event.





Stormwater Structure Maintenance

Stormwater Structure Inspection Schedule

The City of Indianapolis personnel will have the right to enter the premises to perform compliance inspections and maintenance of all permanent stormwater infrastructure. Stormwater structures are considered inlets, outlets, curb turnouts, and all associated components which help transfer stormwater to or from conveyance pipes.

Inspections & Maintenance/Remediation

The following are areas critical for inspection to ensure proper working function of the infrastructure.

Inlet/Outlet Structures (At Least Quarterly, As Needed)

Inspection

- Visually inspect structures inside and out for damage, displacement, and blockage or restricted stormwater flow by any detritus, sediment, or plant material at least four times per year and following rain events in excess of one (1) inch. Identify any floatables or pollutants such as oily sheens, discoloration, and cloudy or muddy water. Also inspect for undercutting around the edges of the structures.

Maintenance

- Remove all debris, trash, floatables, or other material in or around the structures, especially those restricting stormwater flow. If any pipes or structures are blocked, they must be cleared as soon as possible, and the material disposed of properly. Sediment should be removed when the area is completely dry. Disturbed areas need to be immediately stabilized and re-vegetated with appropriate species.

Remediation

- Repair and/or replace any damaged structures or their components to their originally designed condition and elevation. If erosion is occurring, then additional scour protection measures will need to be employed. Areas of severe erosion or other conditions that may constitute a public hazard should be corrected as soon as possible and prior to the next inspection.

Scour Protection Material (At Least Quarterly, As Needed)

Inspection

- Pay close attention for scour along the edges of the stone material adjacent to the structures. This indicates the stone is not acting like a channel and instead forcing runoff to the unprotected edges. This can be caused by debris accumulation, washed away stone, or insufficient width to adequately convey stormwater to or from the structures.

Maintenance

- Remove any debris accumulation. Restore any washed away stone from accumulated piles to areas bare from movement.

Remediation

- Should inspection warrant, remediate insufficient stone quantity with similar material to either widen or lengthen the stone section or restore bare areas where stone is missing. Should the remediation be necessary due to insufficient protection, explore options to enhance protection or lessen erosive velocities. Areas of severe erosion or other conditions that may constitute a public hazard should be corrected as soon as possible and prior to the next inspection.



Stormwater Conveyance Maintenance

Stormwater Conveyance Inspection Schedule

The City of Indianapolis personnel will have the right to enter the premises to perform compliance inspections and maintenance of all permanent stormwater infrastructure. Stormwater infrastructure conveyance in this section includes stormwater pipes.

Inspections & Maintenance/Remediation

The following are areas critical for inspection to ensure proper working function of the infrastructure:

Stormwater Pipes (At Least Quarterly, As Needed)

Inspection

- To the greatest extent possible, visually inspect pipes for damage, displacement, and blockage or restricted stormwater flow by any detritus, sediment, or plant material at least four times per year and following rain events in excess of one (1) inch. Note the amount of sediment and/or debris accumulation within pipes on the inspection report. Identify any floatables or pollutants such as oily sheens, discoloration, and cloudy or muddy water.

Maintenance

- Remove all debris, trash, floatables, or other material in or around the pipes, especially those restricting stormwater flow. If any pipes or structures are blocked, they must be cleared as soon as possible, and the material disposed of properly. Sediment and any other debris should be removed from the pipe before 10% of the pipe diameter is blocked. Disturbed areas need to be immediately stabilized and re-vegetated with appropriate species.

Remediation

- Repair and/or replace any damaged structures or their components to their originally designed condition and elevation. If erosion is occurring, then additional scour protection measures will need to be employed. Areas of severe erosion or other conditions that may constitute a public hazard should be corrected as soon as possible and prior to the next inspection.



Spill Response Plan

The proposed land use will consist of single-family residential houses. The pollutants and sources of each pollutant normally expected from this type of land use are listed below:

- Pollutant Source: Passenger vehicles, delivery vehicles, and trucks
 - Type of Pollutant: Oil, gasoline, diesel fuel, any hydrocarbon associated with vehicular fuels and lubricants, grease, antifreeze, windshield cleaner solution, brake fluid, brake dust, rubber, glass, metal and plastic fragments, grit, road de-icing materials
- Pollutant Source: Residence
 - Type of Pollutant: Cleaning solutions or solvents, leaks from HVAC equipment, grit from roof drainage, aggregate or rubber fragments from roofing system
- Pollutant Source: Roadway
 - Type of Pollutant: Any pollutant associated with vehicular sources, grit from asphalt wearing surface, bituminous compounds from periodic maintenance (sealing, resurfacing, and patching), pavement de-icing materials, wind-blown litter from off-site sources, and elevated water temperatures from contact with impervious surfaces
- Pollutant Source: Lawn and landscape areas
 - Type of Pollutant: Fertilizers, herbicides, organic material (leaves, mulch, grass clippings) and pesticides.

In case of spill, contact the City of Indianapolis Fire Department (317-736-3650), City of Indianapolis Department of Public Works (888-736-3640), and the IDEM Spill Hotline (317-233-7745).

Responsible Parties

The following owner information is responsible for funding and maintenance of the BMP's listed in the manual:

Owner's Name: TMK Development, LLC
Owner's Address: 9335 Forgotten Creek Drive
Indianapolis, IN 46260



Page Intentionally Left Blank



Appendix A – Inspection & Maintenance Checklists

Introduction

This appendix contains sample checklists meant to guide the process and documentation of inspections and maintenance of the BMPs mentioned within this manual for The Ridge on Williams Creek Subdivision. The checklists help to identify areas of the BMPs that require ongoing maintenance and the minimum frequency of inspections that should be completed. It is recommended that inspections be completed by a licensed professional engineer (PE) and/or person with sufficient operational knowledge of the BMPs design and function. Refer to the latest edition of the City of Indianapolis, Indiana Stormwater Technical Standards Manual for additional information.

The checklists in this appendix include:

- Dry Detention BMP Inspection and Maintenance Checklist
- Wet Pond BMP Inspection and Maintenance Checklist
- Water Quality Unit Inspection and Maintenance Log
- Stormwater Infrastructure: Structure Inspection and Maintenance Checklist
- Stormwater Infrastructure: Conveyance Inspection and Maintenance Checklist



Dry Detention BMP Inspection and Maintenance Checklist

Checklist to be completed monthly and within 48 hours of significant rainfall events resulting in 1 or more inch of rain within a 24 hour period.

Site Name _____

BMP – ID _____

“As Built” Plans Available? _____

Inspection Date _____ Inspection Time _____

Days Since Previous Rainfall _____ Depth of Previous Rainfall _____

Inspector _____ Inspector Signature _____

Maintenance Item	Satisfactory or Unsatisfactory	Recommended Inspection Frequency	Notes
<i>Inlet/Outlet Pipes & Structures</i>			
Inspect pipes and structures for proper functioning, damage, and displacement		Quarterly, As Needed	
Inspect for blockages and sediment or debris accumulation		Quarterly, As Needed	
Remove and dispose of sediment, debris, trash, etc. appropriately		As Needed	
Other: _____			
<i>Scour Protection</i>			
Inspect stone at inlets/outlets for displacement or loss of material and for erosion around the material		Quarterly, As Needed	
Inspect for sediment and debris accumulation		Quarterly, As Needed	
Remove and dispose of sediment, debris, trash, etc. appropriately		As Needed	
Inspect for weed intrusion		Quarterly	
Other: _____			
<i>Embankments & Spillway</i>			
Inspect slopes for erosion and structural integrity		Biannually, As Needed	
Inspect slopes for burrowing or tunneling of mammals		Biannually	
Other: _____			



Prairie (Post-Establishment Period)

Inspect for weeds and invasive species		Biannually, As Needed	
Inspect for visual signs of plant cover, die-off, and overall health		Monthly, As Needed	
Inspect plant heights to determine mowing needs		Monthly, As Needed	
Other: _____			

BMP Surface

Inspect for ponding, algae pockets, and improper drainage		Quarterly, As Needed	
Remove trash, debris, & sediment appropriately		As Needed	
Inspect for erosion and improper grades		Quarterly, As Needed	
Other: _____			

Actions to be taken:

To be Completed by (Date):



Wet Detention BMP Inspection and Maintenance Checklist

Checklist to be completed monthly and within 48 hours of significant rainfall events resulting in 1 or more inch of rain within a 24 hour period.

Site Name _____

BMP--ID _____

"As Built" Plans Available? _____

Inspection Date _____ Inspection Time _____

Days Since Previous Rainfall _____ Depth of Previous Rainfall _____

Inspector _____ Inspector Signature _____

Maintenance Item	Satisfactory or Unsatisfactory	Recommended Inspection Frequency	Notes
<i>Inlet/Outlet Pipes & Structures</i>			
Inspect pipes and structures for proper functioning, damage, and displacement		Quarterly, As Needed	
Inspect for blockages and sediment or debris accumulation		Quarterly, As Needed	
Remove and dispose of sediment, debris, trash, etc. appropriately		As Needed	
Other: _____			
<i>Scour Protection</i>			
Inspect stone at inlets/outlets for displacement or loss of material and for erosion around the material		Quarterly, As Needed	
Inspect for sediment and debris accumulation		Quarterly, As Needed	
Remove and dispose of sediment, debris, trash, etc. appropriately		As Needed	
Inspect for weed intrusion		Quarterly	
Other: _____			
<i>Embankments & Spillway</i>			
Inspect slopes for erosion and structural integrity		Biannually, As Needed	
Inspect slopes for burrowing or tunneling of mammals		Biannually	
Other: _____			

Cascade Separator[®] Inspection and Maintenance Guide



CASCADE
separator[®]

Maintenance

The Cascade Separator® system should be inspected at regular intervals and maintained when necessary to ensure optimum performance. The rate at which the system collects sediment and debris will depend upon on-site activities and site pollutant characteristics. For example, unstable soils or heavy winter sanding will cause the sediment storage sump to fill more quickly but regular sweeping of paved surfaces will slow accumulation.

Inspection

Inspection is the key to effective maintenance and is easily performed. Pollutant transport and deposition may vary from year to year and regular inspections will help ensure that the system is cleaned out at the appropriate time. At a minimum, inspections should be performed twice per year (i.e. spring and fall). However, more frequent inspections may be necessary in climates where winter sanding operations may lead to rapid accumulations, or in equipment wash-down areas. Installations should also be inspected more frequently where excessive amounts of trash are expected.

A visual inspection should ascertain that the system components are in working order and that there are no blockages or obstructions in the inlet chamber, flumes or outlet channel. The inspection should also quantify the accumulation of hydrocarbons, trash and sediment in the system. Measuring pollutant accumulation can be done with a calibrated dipstick, tape measure or other measuring instrument. If absorbent material is used for enhanced removal of hydrocarbons, the level of discoloration of the sorbent material should also be identified during inspection. It is useful and often required as part of an operating permit to keep a record of each inspection. A simple form for doing so is provided in this Inspection and Maintenance Guide.

Access to the Cascade Separator unit is typically achieved through one manhole access cover. The opening allows for inspection and cleanout of the center chamber (cylinder) and sediment storage sump, as well as inspection of the inlet chamber and slanted skirt. For large units, multiple manhole covers allow access to the chambers and sump.


The Cascade Separator system should be cleaned before the level of sediment in the sump reaches the maximum sediment depth and/or when an appreciable level of hydrocarbons and trash has accumulated. If sorbent material is used, it must be replaced when significant discoloration has occurred. Performance may be impacted when maximum sediment storage capacity is exceeded. Contech recommends maintaining the system when sediment level reaches 50% of maximum storage volume. The level of sediment is easily determined by measuring the distance from the system outlet invert (standing water level) to the top of the sediment pile. To avoid underestimating the level of sediment in the chamber, the measuring device must be lowered to the top of the sediment pile carefully. Finer, silty particles at the top of the pile typically offer less resistance to the end of the rod than larger particles toward the bottom of the pile. Once this measurement is recorded, it should be compared to the chart in this document to determine if the height of the sediment pile off the bottom of the sump floor exceeds 50% of the maximum sediment storage.

Cleaning

Cleaning of a Cascade Separator system should be done during dry weather conditions when no flow is entering the system. The use of a vacuum truck is generally the most effective and convenient method of removing pollutants from the system. Simply remove the manhole cover and insert the vacuum tube down through the center chamber and into the sump. The system should be completely drained down and the sump fully evacuated of sediment. The areas outside the center chamber and the slanted skirt should also be washed off if pollutant build-up exists in these areas.

In installations where the risk of petroleum spills is small, liquid contaminants may not accumulate as quickly as sediment. However, the system should be cleaned out immediately in the event of an oil or gasoline spill. Motor oil and other hydrocarbons that accumulate on a more routine basis should be removed when an appreciable layer has been captured. To remove these pollutants, it may be preferable to use absorbent pads since they are usually less expensive to dispose than the oil/water emulsion that may be created by vacuuming the oily layer. Trash and debris can be netted out to separate it from the other pollutants. Then the system should be power washed to ensure it is free of trash and debris.


Manhole covers should be securely seated following cleaning activities to prevent leakage of runoff into the system from above and to ensure proper safety precautions. Confined space entry procedures need to be followed if physical access is required. Disposal of all material removed from the Cascade Separator system must be done in accordance with local regulations. In many locations, disposal of evacuated sediments may be handled in the same manner as disposal of sediments removed from catch basins or deep sump manholes. Check your local regulations for specific requirements on disposal. If any components are damaged, replacement parts can be ordered from the manufacturer.



Cascade Separator® Maintenance Indicators and Sediment Storage Capacities

Model Number	Diameter		Distance from Water Surface to Top of Sediment Pile		Sediment Storage Capacity	
	ft	m	ft	m	y ³	m ³
CS-3	3	0.9	1.5	0.5	0.4	0.3
CS-4	4	1.2	2.5	0.8	0.7	0.5
CS-5	5	1.3	3	0.9	1.1	0.8
CS-6	6	1.8	3.5	1	1.6	1.2
CS-8	8	2.4	4.8	1.4	2.8	2.1
CS-10	10	3.0	6.2	1.9	4.4	3.3
CS-12	12	3.6	7.5	2.3	6.3	4.8

Note: The information in the chart is for standard units. Units may have been designed with non-standard sediment storage depth.



A Cascade Separator unit can be easily cleaned in less than 30 minutes.



A vacuum truck excavates pollutants from the systems.

Cascade Separator[®] Inspection & Maintenance Log

Cascade Model:			Location:		
Date	Depth Below Invert to Top of Sediment ¹	Floatable Layer Thickness ²	Describe Maintenance Performed	Maintenance Personnel	Comments

1. The depth to sediment is determined by taking a measurement from the manhole outlet invert (standing water level) to the top of the sediment pile. Once this measurement is recorded, it should be compared to the chart in the maintenance guide to determine if the height of the sediment pile off the bottom of the sump floor exceeds 50% of the maximum sediment storage. Note: to avoid underestimating the volume of sediment in the chamber, the measuring device must be carefully lowered to the top of the sediment pile.
2. For optimum performance, the system should be cleaned out when the floating hydrocarbon layer accumulates to an appreciable thickness. In the event of an oil spill, the system should be cleaned immediately.

SUPPORT

- Drawings and specifications are available at www.ContechES.com.
- Site-specific design support is available from our engineers.

©2021 Contech Engineered Solutions LLC, a QUIKRETE Company

Contech Engineered Solutions LLC provides site solutions for the civil engineering industry. Contech's portfolio includes bridges, drainage, sanitary sewer, stormwater, and earth stabilization products. For information, visit www.ContechES.com or call 800.338.1122

NOTHING IN THIS CATALOG SHOULD BE CONSTRUED AS A WARRANTY. APPLICATIONS SUGGESTED HEREIN ARE DESCRIBED ONLY TO HELP READERS MAKE THEIR OWN EVALUATIONS AND DECISIONS, AND ARE NEITHER GUARANTEES NOR WARRANTIES OF SUITABILITY FOR ANY APPLICATION. CONTECH MAKES NO WARRANTY WHATSOEVER, EXPRESS OR IMPLIED, RELATED TO THE APPLICATIONS, MATERIALS, COATINGS, OR PRODUCTS DISCUSSED HEREIN. ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND ALL IMPLIED WARRANTIES OF FITNESS FOR ANY PARTICULAR PURPOSE ARE DISCLAIMED BY CONTECH. SEE CONTECH'S CONDITIONS OF SALE (AVAILABLE AT WWW.CONTECHES.COM/COS) FOR MORE INFORMATION.



Stormwater Infrastructure: Structure Inspection and Maintenance Checklist

Checklist to be completed monthly and within 48 hours of significant rainfall events resulting in 1 or more inch of rain within a 24 hour period.

Site Name _____

BMP – ID (If Applicable) _____

“As Built” Plans Available? _____

Inspection Date _____ Inspection Time _____

Days Since Previous Rainfall _____ Depth of Previous Rainfall _____

Inspector _____ Inspector Signature _____

Storm Structure #	Debris	Blocked	Condition	Notes
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	
	Y / N	Y / N	Intact / Damaged	

Actions to be Taken:

To be Completed by (Date)



Stormwater Infrastructure: Conveyance Inspection and Maintenance Checklist

Checklist to be completed monthly and within 48 hours of significant rainfall events resulting in 1 or more inch of rain within a 24 hour period.

Site Name _____

BMP – ID: (If Applicable) _____

"As Built" Plans Available? _____

Inspection Date _____ Inspection Time _____

Days Since Previous Rainfall _____ Depth of Previous Rainfall _____

Inspector _____ Inspector Signature _____

Pipe #	Condition	Condition	Notes
	Blocked / Clean	Intact / Damaged	

Actions to be Taken:

To be Completed by (Date)



Appendix B – Invasive Species

Invasive Species

This appendix includes photos of invasive species and a species list that are commonly found within the vegetated areas:





Typha angustifolia
Narrowleaf Cattail



Phalaris arundinacea
Reed Canary Grass



Lythrum salicaria
Purple Loosestrife



Phragmites australis
Common Reed



Cirsium arvense
Canada Thistle



Alliaria petiolata
Garlic Mustard

Below is a list of invasive species that may be found within the vegetated areas:

- Asian Bush Honeysuckle
- Autumn Olive
- Black Locust
- Buckthorn
- Chinese Silvergrass
- Common Reed
- Creeping Charlie
- Creeping Jenny
- Crown Vetch
- Dame's Rocket
- Japanese Hedge Parsley
- Japanese Honeysuckle
- Japanese Knotweed
- Multiflora Rose
- Norway Maple
- Periwinkle
- Privet
- Purple Loosestrife
- Purple Winter Creeper
- Reed Canary Grass
- Russian Olive
- Siberian Elm
- Smooth Brome
- Star-of-Bethlehem
- Sweet Clover
- Tall Fescue
- Tree-of-Heaven
- White Mulberry
- Winged Burning Bush

The link below is an exhaustive list of Indiana's Invasive Plants:
<http://www.in.gov/dnr/naturepreserve/4736.htm>



Appendix C – Ridge at Williams Creek Subdivision Section I Plans and Details

FINAL CONSTRUCTION PLANS

FOR

THE RIDGE ON WILLIAMS CREEK



859 W. 96TH STREET
INDIANAPOLIS, INDIANA

A202400023641

03/28/2024 10:58 AM

FAITH KIMBROUGH
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
By: JN

STORMWATER INFRASTRUCTURE SUMMARY TABLE		
PROPOSED BMPS	CENTER LOCATION	
BMP	1703064.02, 185785.37	
DETENTION BASIN	1703103.92, 185934.46	
WET POND	1703173.38, 186413.88	
PROPOSED STRUCTURE SUMMARY	TOTAL QUANTITY	
12" FES	7	
15" FES	2	
2" Inlet	3	
4" DIA. MH	9	
5" DIA. RESTRICTOR MH	2	
PROPOSED PIPE SUMMARY	DESCRIPTION	LENGTH
ST1-1A - FES 1-1	15" RCP CLASS IV	43'
ST1-1B - ST1-1A	15" RCP CLASS IV	71'
ST1-1 - ST1-1B	15" RCP CLASS IV	104'
ST1-2 - ST1-1	12" RCP CLASS IV	70'
ST1-3 - ST1-2	12" RCP CLASS IV	397'
ST1-4 - ST1-3	12" RCP CLASS IV	110'
ST2-1 - FES 2-1	12" RCP CLASS IV	246'
ST3-1 - FES 3-1	15" RCP CLASS IV	11'
FES 3-1 - ST3-1	12" RCP CLASS IV	19'
FES 4-1 - FES 4-2	12" RCP CLASS IV	89'
FES 4-3 - FES 4-4	12" RCP CLASS IV	76'
ST5-1 - FES 5-1	12" RCP CLASS IV	26'
ST5-2 - ST5-1	12" RCP CLASS IV	44'
ST5-3 - ST5-2	12" RCP CLASS IV	85'
ST5-4 - ST5-3	12" RCP CLASS IV	76'
ST5-5 - ST5-4	12" RCP CLASS IV	62'



PROJECT TEAM

OWNER/DEVELOPER

TMK Development, LLC
9335 Forgotten Creek Drive
Indianapolis, Indiana 46260
Contact: Thomas Kretz

ENGINEER

V3 Companies, Ltd.
619 North Pennsylvania Street
Indianapolis, Indiana 46204
317 423 0690
Project Manager: Jim Rinehart, P.E.
jrinehart@v3co.com
Project Engineer: Matt Vogel,
mvogel@v3co.com

BENCHMARKS

BM #1
FIRE HYDRANT BONNET BOLT ON NORTH SIDE OF PROPERTY
NORTHING: 1703619.892
EASTING: 185886.592
ELEVATION: 809.57
BM #2
RIM OF THE CURB INLET ON WEST SIDE OF SITE ON THE ADJOINERS STREET
NORTHING: 1705395
EASTING: 185616.071
ELEVATION: 803.59

Originating benchmark established with Trimble GPS Survey grade equipment and Indiana CORS Network.
http://incors.in.gov/default.aspx
Elevations NAVD '88
Horizontal Indiana State Plane East Zone.

UTILITY CONTACT INFORMATION

CITIZENS ENERGY GROUP/CWA AUTHORITY, INC.
2150 DR. MARTIN LUTHER KING JR ST INDIANAPOLIS, IN 46202
CONTACT: BRAD HOSTETLER (317) 927-4351



COMPLIANCE INFORMATION

BLOCK:

DEPARTMENT OF
BUSINESS AND NEIGHBORHOOD SERVICES
1200 MADISON AVENUE
INDIANAPOLIS, INDIANA 46225
Ph: (317) 327-8700 Fax: (317)327-3125
DRAINAGE CASE NUMBER: DRN23-01695
FLOOD CASE NUMBER: FLD23-00234

PROFESSIONAL ENGINEER'S CERTIFICATION

I, JIM RINEHART, A LICENSED PROFESSIONAL ENGINEER OF INDIANA, HEREBY CERTIFY THAT THE CIVIL ENGINEERING PLANS WERE PREPARED ON BEHALF OF TMK DEVELOPMENT, LLC BY V3 COMPANIES, LTD. UNDER MY PERSONAL DIRECTION. THIS TECHNICAL SUBMISSION IS INTENDED TO BE USED AS AN INTEGRAL PART OF AND IN CONJUNCTION WITH THE PROJECT SPECIFICATIONS AND CONTRACT DOCUMENTS.
DATED THIS 19th DAY OF March, A.D., 2024.

JIM RINEHART, LICENSED PROFESSIONAL ENGINEER PE#10260495
MY LICENSE EXPIRES ON NOVEMBER 30, 2025



DRAINAGE NOTE: ALL ROOF DRAINS AND DOWNSPOUTS FOR FUTURE HOMES CONSTRUCTED ON LOTS SHALL BE DIRECTED TO THE FRONT YARDS AND INTO OR THROUGH THE STORM CONVEYANCE SYSTEMS. ALL ROOF SURFACES SHALL BE ROUTED THROUGH THE STORMWATER BMP AND DETENTION BASIN AT THE SOUTHWEST CORNER OF THE PROJECT SITE.

INDEX	
CIVIL ENGINEERING PLANS	
C0.0	COVER SHEET
C0.1	GENERAL NOTES, LEGEND, AND ABBREVIATIONS
C1.0 - C1.4	EXISTING CONDITIONS
C2.0 - C2.4	DEMOLITION PLAN
C3.0 - C3.4	GRADING & SITE DEVELOPMENT PLAN
C4.0 - C4.3	STREET PLAN & PROFILES
C4.4	ENTRANCE DETAILS
C4.5 - C4.9	EROSION CONTROL PLAN
C4.10 - C4.11	EROSION CONTROL DETAILS
C4.12 - C4.13	STORM WATER POLLUTION PREVENTION PLAN
C5.0 - C5.5	STORM PLAN & PROFILES, STRUCTURE TABLE
C5.6	COMMON AREA POND CROSS SECTIONS
C5.7 - C5.8	SANITARY PLAN & PROFILES, SANITARY LATERALS
C5.9	WATER PLAN
C6.0 - C6.6	CONSTRUCTION DETAILS
C7.0	EMERGENCY OVERFLOW ROUTING
SUPPORTING DOCUMENTS	
1 of 1	ALTA AND TOPOGRAPHIC SURVEY

REVISIONS		
NO.	DATE	DESCRIPTION
7	02-23-24	REVISED PER CITY COMMENTS
8	03-04-24	REVISED PER CITY COMMENTS
1	10-18-23	REVISED PER CITY COMMENTS
2	10-18-23	REVISED PER CITY COMMENTS
3	11-15-23	REVISED PER CITY COMMENTS
4	11-27-23	REVISED PER CITY COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

PROJECT NO. 220861 S04	
ORIGINAL ISSUE DATE:	07-07-2023
PROJECT MANAGER:	JOR
DESIGNED BY:	MRV
DRAWN BY:	MRV

COVER SHEET	
INDIANAPOLIS	THE RIDGE ON WILLIAMS CREEK

619 N Pennsylvania St
Indianapolis, IN 46204
317.423.0690
www.v3co.com

DRAWING NO. **C0.0**

GENERAL NOTES

- EXISTING SITE TOPOGRAPHY, UTILITIES, RIGHT-OF-WAY AND HORIZONTAL CONTROL SHOWN ON THE DRAWINGS WERE OBTAINED FROM A SURVEY PREPARED BY:
V3 COMPANIES, LTD.
619 N. PENNSYLVANIA AVE.
INDIANAPOLIS, IN 46204
COPIES OF THE SURVEY ARE AVAILABLE FROM THE SURVEYOR. SITE CONDITIONS MAY HAVE CHANGED SINCE THE SURVEY WAS PREPARED. CONTRACTORS TO VISIT SITE TO FAMILIARIZE THEMSELVES WITH THE CURRENT CONDITIONS.
- ALL EXISTING TOPOGRAPHY, UNDERGROUND UTILITIES, STRUCTURES AND ASSOCIATED FACILITIES SHOWN ON THESE DRAWINGS HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS. THEREFORE, THEIR LOCATIONS AND ELEVATIONS MUST BE CONSIDERED APPROXIMATE ONLY. THERE MAY BE OTHER FACILITIES, THE EXISTENCE OF WHICH ARE NOT PRESENTLY KNOWN.
- CONTRACTOR IS TO VERIFY ALL EXISTING STRUCTURES AND FACILITIES AND NOTIFY ENGINEER OF ANY DISCREPANCIES PRIOR TO ORDERING MATERIAL AND STARTING WORK.
- ALL APPLICABLE PROVISIONS OF THE CURRENT OCCUPATIONAL SAFETY AND HEALTH ACT ARE HEREIN INCORPORATED BY REFERENCE.
- THE CONTRACTOR SHALL SUBSCRIBE TO ALL GOVERNING REGULATIONS AND SHALL OBTAIN ALL NECESSARY PUBLIC AGENCY PERMITS PRIOR TO STARTING WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FOR CONSTRUCTION ALONG OR ACROSS EXISTING STREETS OR HIGHWAYS. CONTRACTOR SHALL MAKE ARRANGEMENTS FOR THE PROPER BRACING, SHORING AND OTHER REQUIRED PROTECTION OF ALL ROADWAYS BEFORE CONSTRUCTION BEGINS. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE STREETS OR ROADWAYS AND ASSOCIATED STRUCTURES AND SHALL MAKE REPAIRS AS NECESSARY TO THE SATISFACTION OF THE OWNER OF THE ROADWAY.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES AND TRAFFIC CONTROL PHASES OF CONSTRUCTION. BARRICADES AND WARNING SIGNS SHALL BE PROVIDED IN ACCORDANCE WITH THE INDOT STANDARD SPECIFICATIONS. ALL TRAFFIC CONTROL WORK SHALL BE DONE IN ACCORDANCE WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
- EXCEPT WHERE MODIFIED BY THE CONTRACT DOCUMENTS, ALL WORK PROPOSED HEREON SHALL BE IN ACCORDANCE WITH THE FOLLOWING SPECIFICATIONS WHICH ARE HEREBY MADE A PART HEREOF:
 - INDIANA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS" AS PREPARED BY INDOT, LATEST EDITION.
 - "CITIZENS ENERGY GROUP WATER STANDARDS" LATEST EDITION.
 - "CITIZENS ENERGY GROUP SANITARY STANDARDS" LATEST EDITION.
 - THE LATEST EDITIONS OF THE MUNICIPAL CODE AND STANDARDS OF THE CITY OF INDIANAPOLIS.
 - THE NATIONAL ELECTRIC CODE.
 - THE INDIANA ACCESSIBILITY CODE.
- IN THE EVENT OF CONFLICTING SPECIFICATIONS WITH REGARD TO SITE WORK ISSUES DESIGNED BY THE ENGINEER, THE MORE STRINGENT REQUIREMENT SHALL GOVERN.
- THE CONTRACTOR SHALL NOTIFY THE AUTHORITY HAVING JURISDICTION AT LEAST 48 HOURS PRIOR TO COMMENCING ANY WORK AND FOR ANY NEW CONSTRUCTION REQUIRING INSPECTION.
- ALL TREES TO BE SAVED SHALL BE IDENTIFIED PRIOR TO CONSTRUCTION AND SHALL BE PROTECTED PER INDOT STANDARDS. THE RIGHT-OF-WAY LINE AND LIMITS OF THE CONTRACTOR'S OPERATIONS SHALL BE CLEARLY DEFINED THROUGHOUT THE CONSTRUCTION PERIOD. ALL TREES IDENTIFIED TO REMAIN SHALL BE PROTECTED FROM DAMAGE INCLUDING TRUNKS, BRANCHES AND ROOTS. NO EXCAVATING, FILLING OR GRADING IS TO BE DONE INSIDE THE DRIP LINE OF TREES UNLESS OTHERWISE INDICATED.
- CONSTRUCTION ACCESS POINTS TO THE SITE SHALL BE PROTECTED IN SUCH A WAY AS TO PREVENT ACCUMULATION OF MUD OR SOIL ON PUBLIC THOROUGHFARES. AT THE END OF EACH DAY AND AS OFTEN AS OTHERWISE NECESSARY THE CONTRACTOR SHALL CLEAN UP ALL MUD OR SOIL WHICH HAS BEEN TRACKED ONTO PUBLIC STREETS AS REQUIRED BY THE AUTHORITIES HAVING JURISDICTION AND AS DETAILED IN THE STORM WATER POLLUTION PREVENTION PLAN, SHEETS C4.10 AND C4.11.
- THE CONTRACTOR SHALL PROVIDE FOR THE SAFE AND ORDERLY PASSAGE OF TRAFFIC AND PEDESTRIANS WHERE FISHERY PARKING AND THOROUGHFARES AND ADJACENT PROPERTIES ARE IN ACCORDANCE WITH THE CITY OF INDIANAPOLIS MUNICIPAL CODE AND INDOT REQUIREMENTS.


- NO HOLES ARE TO BE LEFT OPEN IN THE PAVEMENT OR PARKWAY OVER A HOLIDAY, WEEKEND OR AFTER 3:00 P.M. ON THE DAY PRECEDING A HOLIDAY OR A WEEKEND.
- ALL EXISTING PAVEMENT OR CONCRETE TO BE REMOVED SHALL BE SAWCUT ALONG LIMITS OF PROPOSED REMOVAL BEFORE COMMENCEMENT OF PAVEMENT REMOVAL.
- REMOVED PAVEMENT, SIDEWALK, CURB AND GUTTER, ETC. SHALL BE LEGALLY DISPOSED OF BY THE CONTRACTOR AS PART OF THE BASE CONTRACT.
- NO BURNING OR INCINERATION OF RUBBISH WILL BE PERMITTED ON SITE.
- FOR REGULATED UTILITY LOCATIONS, THE CONTRACTOR SHALL CONTACT INDIANAPOLIS AT 811 OR 800-382-5844. LOCAL GOVERNMENT AGENCIES SHOULD BE CONTACTED BY THE CONTRACTOR FOR LOCATION OF ALL NONREGULATED UTILITY LOCATIONS. CALL FOR LOCATIONS AT LEAST 48 HOURS IN ADVANCE OF CONSTRUCTION.
- BEFORE EXCAVATING OVER OR ADJACENT TO ANY EXISTING UTILITIES, THE CONTRACTOR SHALL NOTIFY THE OWNER OF SUCH UTILITIES TO ENSURE THAT PROTECTIVE WORK WILL BE COORDINATED AND PERFORMED BY THE CONTRACTOR IN ACCORDANCE WITH THE REQUIREMENTS OF THE OWNER OF THE UTILITY INVOLVED. IF ANY EXISTING SERVICE LINES, UTILITIES AND UTILITY STRUCTURES WHICH ARE TO REMAIN IN SERVICE ARE UNCOVERED OR ENCOUNTERED DURING THIS OPERATION, THEY SHALL BE SAFEGUARDED, PROTECTED FROM DAMAGE AND SUPPORTED IF NECESSARY.
- THE CONTRACTOR IS RESPONSIBLE FOR HAVING A SET OF "APPROVED" ENGINEERING PLANS WITH THE LATEST REVISION DATE ON THE JOB SITE PRIOR TO THE START OF CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR EROSION AND SEDIMENTATION CONTROL AS DETAILED IN THE STORM WATER POLLUTION PREVENTION PLAN.
- ALL CURB RADIUS REFER TO BACK OF CURB.
- ANY AREAS THAT ARE DISTURBED DURING CONSTRUCTION SHALL BE RESTORED IN CONFORMANCE WITH THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION AND SHALL BE INCIDENTAL TO THE CONTRACT.
- STREET PAVING AND CURBS TO REMAIN SHALL BE PROTECTED FROM DAMAGE AND IF DAMAGED, SHALL BE REPLACED PROMPTLY IN CONFORMANCE WITH THE CITY OF INDIANAPOLIS OR INDOT STANDARD SPECIFICATIONS IN MATERIALS AND WORKMANSHIP.
- PROPOSED ELEVATIONS INDICATE FINISHED CONDITIONS. FOR ROUGH GRADING ELEVATIONS ALLOW FOR THICKNESS OF PROPOSED PAVING (ROADS, WALKS, DRIVES, ETC.) OR TOPSOIL AS INDICATED ON DRAWINGS.
- CAD FILES ARE AVAILABLE FOR CONSTRUCTION LAYOUT UPON REQUEST.
- BACKFILL SHALL BE PLACED NEXT TO THE CURB AS SOON AS PERMISSIBLE AFTER CONSTRUCTION TO PREVENT SCOURING AND UNDERCUTTING BY STORM WATER RUNOFF.
- BUTT JOINTS SHALL BE PROVIDED WHEREVER NEW PAVEMENT ABUTS EXISTING PAVEMENT. ALL BUTT JOINTS SHALL BE CONSTRUCTED BY MILLING AND SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE BITUMINOUS SURFACE COURSE.
- WHEN AN EXISTING DRAINAGE ROUTE, EITHER A STORM SEWER OR WATERWAY, IS INTERRUPTED DUE TO CONSTRUCTION, THE DRAINAGE ROUTE SHALL BE REESTABLISHED TO ORIGINAL CONDITIONS BY THE END OF THE SAME WORK DAY. POSITIVE DRAINAGE MUST BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION.
- PROVIDE SMOOTH VERTICAL CURVES THROUGH HIGH AND LOW POINTS INDICATED BY SPOT ELEVATIONS. PROVIDE UNIFORM SLOPES BETWEEN NEW AND EXISTING GRADES. AVOID RIDGES AND DEPRESSIONS.
- FINAL ADJUSTMENT OF FIRE HYDRANTS, VALVE VAULTS AND MANHOLES TO FINISHED GRADE ARE INCIDENTAL TO THEIR COST.
- ANY EXISTING UTILITY STRUCTURES REQUIRING ADJUSTMENT ARE TO BE ADJUSTED OR RECONSTRUCTED BY THE CONTRACTOR TO THE UTILITY OWNER'S SATISFACTION. ADJUSTMENTS OR RECONSTRUCTIONS NOT CALLED FOR ON THE PLANS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- ALL UTILITY CONNECTIONS TO EXISTING LINES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE REGULATIONS AND TO THE SATISFACTION OF THE UTILITY OWNER.
- PROVIDE TRENCH BACKFILL IN ACCORDANCE WITH THE DETAILS OF THE PLANS FOR ALL UTILITY LINES (OR AS OTHERWISE NOTED ON PLANS). BACKFILL SHALL BE PLACED AND COMPACTED PER THE CITY OF INDIANAPOLIS AND INDOT SPECIFICATIONS. COST OF BACKFILL IS TO BE CONSIDERED INCIDENTAL TO THE UTILITY WORK.
- ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- PRIOR TO DEMOBILIZATION, ALL WORK SHALL BE CLEANED AND INSPECTED TO THE SATISFACTION OF THE AUTHORITY HAVING JURISDICTION. THE COST OF THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- THE GENERAL CONTRACTOR SHALL COORDINATE WITH UTILITY COMPANIES TO PROVIDE CABLE TV, PHONE, ELECTRIC, GAS AND IRRIGATION SERVICES. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR SECURING SITE LAYOUTS FOR THESE UTILITIES AND SHALL COORDINATE AND PROVIDE CONDUIT CROSSINGS AS REQUIRED. THIS COORDINATION SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. ANY

- CONFLICTS IN UTILITIES SHALL BE CORRECTED BY THE GENERAL CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- BAND-SEAL CONNECTORS OR EQUIVALENT SHALL BE USED TO JOIN PIPES OF DISSIMILAR MATERIAL.
- CONTRACTOR SHALL MAINTAIN ACCURATE RECORDS OF ALL CONSTRUCTION IN CONFORMANCE WITH ALL MUNICIPAL AND CLIENT REQUIREMENTS FOR USE IN PREPARING RECORD DRAWINGS.
- THE SUBCONTRACTOR SHALL INSTALL A 2"x4"x6" POST ADJACENT TO THE TERMINUS OF UTILITY MAINS AND SERVICE LINES. POSTS SHALL BE MARKED IN ACCORDANCE WITH THE VILLAGE STANDARDS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEWATERING ANY EXCAVATION. ANY DEWATERING REQUIRED SHALL BE INCIDENTAL TO THE CONTRACT.
- COPIES OF SOILS INVESTIGATION REPORTS MAY BE OBTAINED FROM THE OWNER. REQUEST FOR SPECIAL CONSTRUCTION METHODS REQUIRED IN ORDER TO INSTALL THE PROPOSED IMPROVEMENTS SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE PROJECT. ANY ADDITIONAL SOILS DATA NEEDED TO CONFIRM THE CONTRACTOR'S OPINIONS OF THE SUBSOIL CONDITIONS SHALL BE DONE AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR SHALL OBTAIN THE OWNER'S WRITTEN AUTHORIZATION TO ACCESS THE SITE TO CONDUCT A SUPPLEMENTAL SOILS INVESTIGATION.
- ALL FIELD TILE ENCOUNTERED DURING CONSTRUCTION OPERATIONS SHALL BE CONNECTED TO THE PROPOSED STORM SEWER OR EXTENDED TO OUTLET INTO A PROPOSED DRAINAGE WAY AS DETERMINED BY THE ENGINEER. IF THIS CANNOT BE ACCOMPLISHED, THEN IT SHALL BE REPAIRED WITH NEW PIPE OF SIMILAR SIZE AND MATERIAL TO THE ORIGINAL LINE AND PUT IN ACCEPTABLE OPERATIONAL CONDITION. A RECORD OF THE LOCATION OF ALL FIELD TILE FOR ON-SITE DRAIN PIPE ENCOUNTERED SHALL BE KEPT BY THE SUBCONTRACTOR AND SUBMITTED TO THE ENGINEER UPON COMPLETION OF THE PROJECT. ALL FIELD TILE REPAIRS SHALL BE CONSIDERED AS INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE PROVIDED.
- THE ENGINEER AND OWNER ARE NOT RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, TIME OF PERFORMANCE, PROGRAMS OR FOR ANY SAFETY PRECAUTIONS USED BY THE CONTRACTOR. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR EXECUTION OF HISHER WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND SPECIFICATIONS.

A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
By: JN



LEGEND



ABBREVIATIONS

DESCRIPTION	PROPOSED	EXISTING
RIGHT-OF-WAY LINE	---	---
PROPERTY LINE (EXTERIOR)	---	---
LOT LINE (INTERIOR)	---	---
EASEMENT LINE	---	---
FENCE LINE	---	---
CENTERLINE	---	---
PROPERTY CORNER	□	□
CONTOUR	710	710
CURB & GUTTER	---	---
DEPRESSED CURB & GUTTER	---	---
REVERSE PITCHED CURB	---	---
SPOT ELEVATION	x 706.00	x 706.00
TOP OF CURB ELEVATION	782.82	782.82
EDGE OF PAVEMENT ELEVATION	782.12	782.12
UTILITY STUB	---	---
SANITARY SEWER	---	---
SANITARY FORCE MAIN	---	---
STORM SEWER	---	---
WATER MAIN	---	---
GAS MAIN	---	---
UNDERGROUND TELEPHONE & ELECTRIC DUCT BANK	---	---
BURIED CABLE-ELECTRIC	---	---
BURIED CABLE-TELEPHONE	---	---
ATLAS LOCATED UTILITY	---	---
UTILITY STRUCTURE WITH CLOSED LID	---	---
CURB INLET	---	---
DRAINAGE STRUCTURE WITH OPEN LID	---	---
FIRE HYDRANT	---	---
VALVE IN VALVE BOX	---	---
GATE VALVE IN VALVE VAULT	---	---
POST INDICATOR VALVE	---	---
THRUST BLOCK	---	---
TREE	---	---
TREE LINE	---	---
CONCRETE HEADWALL	---	---
SUBMERGED HEADWALL	---	---
FLARED END SECTION (F.E.S.)	---	---
GUY WIRES	---	---
FLOOD LIGHT	---	---
UTILITY POLE	---	---
LIGHT STANDARD	---	---
TRAFFIC SIGNAL POLE	---	---
HAND HOLE	---	---
SOIL BORING	---	---
IRRIGATION HEADS	---	---
SIGN	---	---
TELEPHONE MANHOLE	---	---
MONITORING WELL	---	---
TELEPHONE PEDESTAL	---	---
TRANSFORMER PAD	---	---
UTILITY TO BE ABANDONED	---	---
FEATURE TO BE REMOVED	---	---
STORMWATER FLOW DIRECTION	---	---
STORMWATER OVERFLOW ROUTE	---	---
DITCH CHECK	---	---
INLET FILTER BASKET	---	---
RIP RAP	---	---
BOLLARD	---	---
SILT FENCE	---	---
WATER MAIN PROTECTION	---	---
UTILITY CROSSING LABEL	---	---
GUARDRAIL	---	---
RAILROAD TRACKS	---	---
RETAINING WALL	---	---
REVISION DELINEATION	---	---
CONSTRUCTION LIMIT LINE	---	---
TREE PROTECTION FENCE	---	---

GENERAL NOTES, LEGEND AND ABBREVIATIONS

PROJECT NO.: 220861 S04
ORIGINAL ISSUE DATE: 07-07-2023

REVISIONS

NO.	DATE	DESCRIPTION
7	02-23-24	REVISED PER CITY COMMENTS
8	03-04-24	REVISED PER CITY COMMENTS
9	03-04-24	REVISED PER CITY COMMENTS
10	03-04-24	REVISED PER CITY COMMENTS
11	03-04-24	REVISED PER CITY COMMENTS
12	03-04-24	REVISED PER CITY COMMENTS
13	03-04-24	REVISED PER CITY COMMENTS
14	03-04-24	REVISED PER CITY COMMENTS
15	03-04-24	REVISED PER CITY COMMENTS
16	03-04-24	REVISED PER CITY COMMENTS
17	03-04-24	REVISED PER CITY COMMENTS
18	03-04-24	REVISED PER CITY COMMENTS
19	03-04-24	REVISED PER CITY COMMENTS
20	03-04-24	REVISED PER CITY COMMENTS
21	03-04-24	REVISED PER CITY COMMENTS
22	03-04-24	REVISED PER CITY COMMENTS
23	03-04-24	REVISED PER CITY COMMENTS
24	03-04-24	REVISED PER CITY COMMENTS
25	03-04-24	REVISED PER CITY COMMENTS
26	03-04-24	REVISED PER CITY COMMENTS
27	03-04-24	REVISED PER CITY COMMENTS
28	03-04-24	REVISED PER CITY COMMENTS
29	03-04-24	REVISED PER CITY COMMENTS
30	03-04-24	REVISED PER CITY COMMENTS
31	03-04-24	REVISED PER CITY COMMENTS
32	03-04-24	REVISED PER CITY COMMENTS
33	03-04-24	REVISED PER CITY COMMENTS
34	03-04-24	REVISED PER CITY COMMENTS
35	03-04-24	REVISED PER CITY COMMENTS
36	03-04-24	REVISED PER CITY COMMENTS
37	03-04-24	REVISED PER CITY COMMENTS
38	03-04-24	REVISED PER CITY COMMENTS
39	03-04-24	REVISED PER CITY COMMENTS
40	03-04-24	REVISED PER CITY COMMENTS
41	03-04-24	REVISED PER CITY COMMENTS
42	03-04-24	REVISED PER CITY COMMENTS
43	03-04-24	REVISED PER CITY COMMENTS
44	03-04-24	REVISED PER CITY COMMENTS
45	03-04-24	REVISED PER CITY COMMENTS
46	03-04-24	REVISED PER CITY COMMENTS
47	03-04-24	REVISED PER CITY COMMENTS
48	03-04-24	REVISED PER CITY COMMENTS
49	03-04-24	REVISED PER CITY COMMENTS
50	03-04-24	REVISED PER CITY COMMENTS
51	03-04-24	REVISED PER CITY COMMENTS
52	03-04-24	REVISED PER CITY COMMENTS
53	03-04-24	REVISED PER CITY COMMENTS
54	03-04-24	REVISED PER CITY COMMENTS
55	03-04-24	REVISED PER CITY COMMENTS
56	03-04-24	REVISED PER CITY COMMENTS
57	03-04-24	REVISED PER CITY COMMENTS
58	03-04-24	REVISED PER CITY COMMENTS
59	03-04-24	REVISED PER CITY COMMENTS
60	03-04-24	REVISED PER CITY COMMENTS

DESIGNED BY: M/RV
DRAWN BY: M/RV

INDIANAPOLIS

THE RIDGE ON WILLIAMS CREEK

ABBREVIATIONS

INDIANAPOLIS

619 N Pennsylvania Street
Indianapolis, IN 46204
www.v3co.com

INDIANAPOLIS

DRAWING NO. **C0.1**



619 N Pennsylvania Street
 Indianapolis, IN 46204
 317.423.0690
 www.v3co.com

DRAWING NO.
C3.0


**GRADING & SITE DEVELOPMENT
 PLAN**
THE RIDGE ON WILLIAMS CREEK
 INDIANAPOLIS

NO.	DATE	DESCRIPTION
1	09-15-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY AND CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
4	11-27-23	REVISED PER CITY AND CITIZENS COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS


NO.	DATE	DESCRIPTION
7	02-23-24	REVISED PER CITY COMMENTS
8	03-04-24	REVISED PER CITY COMMENTS

- NOTES:
- ALL ELEVATIONS SHOWN DEPICT FINISHED GRADE UNLESS OTHERWISE NOTED. SUBTRACT TOPSOIL THICKNESS OR PAVEMENT SECTION TO ESTABLISH SUBGRADE ELEVATIONS.
 - ALL DIMENSIONS SHOWN ARE TO EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
 - ALL CURB AND GUTTER SHALL BE COMBINED CURB AND GUTTER PER INDOT STANDARD DRAWING NO. E 605-CCCC-01 UNLESS OTHERWISE NOTED.



MATCHLINE - SEE BELOW



MATCHLINE - SEE SHEET C3.1



MATCHLINE - SEE ABOVE



KEY MAP
 N.T.S.

PAVING LEGEND

REGULAR HMA PAVEMENT	
[Symbol]	1.5" HMA SURFACE COURSE, 9.5mm
[Symbol]	1.5" HMA INTERMEDIATE COURSE, 19.0mm
[Symbol]	4" HMA BASE COURSE, 25.0mm
[Symbol]	6" AGGREGATE BASE COURSE - TYPE IIIA

COLLECTOR STREET HMA PAVEMENT	
[Symbol]	1.5" HMA, 3.70 SURFACE COURSE, 9.5mm
[Symbol]	2.5" HMA, 3.64 INTERMEDIATE COURSE, 19.0mm
[Symbol]	3.5" HMA, 3.64 BASE COURSE, 25.0mm
[Symbol]	2.5" HMA, 3.76 INTERMEDIATE COURSE, OG 19.0mm
[Symbol]	3.0" HMA, 3.64 BASE COURSE, 25.0mm
[Symbol]	INDOT SUBGRADE TREATMENT, TYPE IC




03/28/2024 10:58 AM
 FAITH KIMBROUGH
 MARION COUNTY IN RECORDER
 FEE: \$ 140.00
 PAGES: 60
 By: JN



MATCHLINE - SEE SHEET C3.0

MATCHLINE - SEE SHEET C3.3



CALIFORNIA LOT
 56,791 SF
 1.304 AC
 MFPG = 805.83

MONTANA LOT
 110,583 SF
 2.539 AC
 MFPG = 815.08

OREGON LOT
 54,564 SF
 1.253 AC
 MFPG FRONT = 815.08
 MFPG BACK = 804.59

REVISIONS	
NO.	DATE
8	03/04/24
7	02/23/24
6	02/09/24
5	01/09/24
4	11/27/23
3	11/15/23
2	10/18/23
1	09/16/23

DESCRIPTION	
8	REVISED PER CITY COMMENTS
7	REVISED PER CITY COMMENTS
6	REVISED PER CITY COMMENTS
5	REVISED PER CITY COMMENTS
4	REVISED PER CITY COMMENTS
3	REVISED PER CITY COMMENTS
2	REVISED PER CITY COMMENTS
1	REVISED PER CITY COMMENTS

PROJECT INFORMATION	
PROJECT NO.	220851 S04
PROJECT MANAGER	JOR
DESIGNED BY	MRY
DRAWN BY	MRY
CHECKED BY	
DATE	07-07-2023

GRADING & SITE DEVELOPMENT PLAN

THE RIDGE ON WILLIAMS CREEK

INDIANAPOLIS

619 N Pennsylvania Street
 Indianapolis, IN 46204
 317.423.0690
 www.v3co.com

DRAWING NO. **C3.1**

KEY MAP

GRAPHIC SCALE
 1" = 20'

PAVING LEGEND

REGULAR HMA PAVEMENT	
[Symbol]	1.5" HMA SURFACE COURSE, 9.5mm
[Symbol]	1.5" HMA INTERMEDIATE COURSE, 19.0mm
[Symbol]	4" HMA BASE COURSE, 25.0mm
[Symbol]	6" AGGREGATE BASE COURSE - TYPE IIA

A202400023641

03/28/2024 10:58 AM

FAITH KIMBROUGH

MARION COUNTY IN RECORDER

INDIANA 811

Know what's below. Call before you dig.

FEE: \$ 140.00
 PAGES: 60
 By: JN


SEAL OF THE STATE OF INDIANA
 ENGINEER
 FAITH KIMBROUGH
 No. 12345

MATCHLINE - SEE SHEET C3.2

- NOTES:**
- ALL ELEVATIONS SHOWN DEPICT FINISHED GRADE UNLESS OTHERWISE NOTED. SUBTRACT TOPSOIL THICKNESS OR PAVEMENT SECTION TO ESTABLISH SUBGRADE ELEVATIONS.
 - ALL DIMENSIONS SHOWN ARE TO EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
 - ALL CURB AND GUTTER SHALL BE COMBINED CURB AND GUTTER PER INDOT STANDARD DRAWING NO. E 605-CCC-01 UNLESS OTHERWISE NOTED.
 - ALL FUTURE LAND DISTURBANCE ON CALIFORNIA, MONTANA, AND OREGON LOTS MUST DRAIN TO SOUTHWEST BASIN FOR WATER QUALITY AND DETENTION REQUIREMENTS.
 - ALL FUTURE SUBSTANTIAL IMPROVEMENTS TO THE CALIFORNIA, MONTANA, AND OREGON LOTS, INCLUDING THE ADDITION OF NEW STRUCTURES, SHALL HAVE AT LEAST 2 FEET OF VERTICAL SEPARATION FROM THE LOWEST GROUND ELEVATION NEXT TO A STRUCTURE TO THE 100-YEAR FLOOD ELEVATION. MINIMUM FLOOD PROTECTION GRADES (MFPG) ARE PROVIDED ON EACH LOT SHOWN ABOVE. THE BASE FLOOD ELEVATION VARIES ALONG THE LENGTH OF THIS PROJECT AND ELEVATIONS ARE PROVIDED ABOVE. BASED ON THE MARION COUNTY, INDIANA FLOOD INSURANCE STUDY DATED APRIL 16TH, 2016.
 - ALL ROOF DRAINS AND DOWNSPOUTS FOR FUTURE HOMES CONSTRUCTED ON LOTS SHALL BE DIRECTED TO THE FRONT YARDS AND INTO OR THROUGH THE STORM COVERS OF STORMWATER BASINS. ALL ROOF SURFACES SHALL BE ROUTED THROUGH THE STORMWATER BMP AND DETENTION BASIN AT THE SOUTHWEST CORNER OF THE PROJECT SITE.

MATCHLINE - SEE SHEET C3.1

MATCHLINE - SEE SHEET C3.3



MATCHLINE - SEE SHEET C3.4


- NOTES:
1. ALL ELEVATIONS SHOWN DEPICT FINISHED GRADE UNLESS OTHERWISE NOTED. SUBTRACT TOPSOIL THICKNESS OR PAVEMENT SECTION TO ESTABLISH SUBGRADE ELEVATIONS.
 2. ALL DIMENSIONS SHOWN ARE TO EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
 3. ALL CURB AND GUTTER SHALL BE COMBINED CURB AND GUTTER PER INDOT STANDARD DRAWING NO. E 605-CCGG-01 UNLESS OTHERWISE NOTED.
 4. ALL FUTURE LAND DISTURBANCE ON WASHINGTON, COLORADO, AND UTAH LOTS MUST DRAIN TO SOUTHWEST BASIN FOR WATER QUALITY AND DETENTION REQUIREMENTS.
 5. ALL FUTURE SUBSTANTIAL IMPROVEMENTS TO THE WASHINGTON, COLORADO, AND UTAH LOTS, INCLUDING THE ADDITION OF NEW STRUCTURES, SHALL BE CONSTRUCTED WITH A MINIMUM OF 2 FEET OF VERTICAL SEPARATION FROM THE LOWEST GROUND ELEVATION. STRUCTURES TO THE 100-YEAR HIGH WATER ELEVATION, THEY MUST ALSO HAVE A LOWEST ELEVATION A MINIMUM OF 2 FEET ABOVE THE BASE FLOOD ELEVATION. MINIMUM FLOOD PROTECTION GRADES (MFPFG) ARE PROVIDED ON EACH LOT SHOWN ABOVE.
 6. THE BASE FLOOD ELEVATION ESTABLISHED AT THE SOUTHWEST CORNER OF THE PROPERTY WAS DETERMINED VIA HEC-RAS MODELING OF THE WATERSHED AND HOOPER RUN BY V3.
 7. ALL ROOF DRAINS AND DOWNSPOUTS FOR FUTURE HOMES CONSTRUCTED ON LOTS SHALL BE DIRECTED TO THE FRONT YARDS AND INTO OR THROUGH EXISTING STORMWATER SYSTEMS. ROOF SURFACES SHALL BE ROUTED THROUGH THE STORMWATER BMP AND DETENTION BASIN AT THE SOUTHWEST CORNER OF THE PROJECT SITE.




PAVING LEGEND

REGULAR HMA PAVEMENT

- 1.5" HMA SURFACE COURSE, 9.5mm
- 1.5" HMA INTERMEDIATE COURSE, 18.0mm
- 4" HMA BASE COURSE, 25.0mm
- 6" AGGREGATE BASE COURSE - TYPE IIIA



A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
SEE: \$ 140.00
PAGES: 60
By: JN



KEY MAP
N.T.S.

INDIANAPOLIS		THE RIDGE ON WILLIAMS CREEK	
619 N Pennsylvania Street Indianapolis, IN 46204 317.423.0950 www.v3co.com		INDIANA	
DRAWN BY: MRV		PROJECT NO.: 220851 S04	
DESIGNED BY: MRV		PROJECT MANAGER: JOR	
REVISED PER CITY COMMENTS		NO. DATE	
REVISED PER CITY COMMENTS		1 09-15-23 REVISED PER CITY AND CITIZENS COMMENTS	
REVISED PER CITY COMMENTS		2 10-18-23 REVISED PER CITY AND CITIZENS COMMENTS	
REVISED PER CITY COMMENTS		3 11-15-23 REVISED PER CITY AND CITIZENS COMMENTS	
REVISED PER CITY COMMENTS		4 11-27-23 REVISED PER CITY COMMENTS	
REVISED PER CITY COMMENTS		5 01-08-24 REVISED PER CITY COMMENTS	
REVISED PER CITY COMMENTS		6 02-09-24 REVISED PER CITY COMMENTS	
NO. DATE		DESCRIPTION	
7 02-23-24		REVISED PER CITY COMMENTS	
8 03-04-24		REVISED PER CITY COMMENTS	
NO. DATE		DESCRIPTION	
1 09-15-23		REVISED PER CITY AND CITIZENS COMMENTS	
2 10-18-23		REVISED PER CITY AND CITIZENS COMMENTS	
3 11-15-23		REVISED PER CITY AND CITIZENS COMMENTS	
4 11-27-23		REVISED PER CITY COMMENTS	
5 01-08-24		REVISED PER CITY COMMENTS	
6 02-09-24		REVISED PER CITY COMMENTS	

DRAWING NO. **C3.2**


INDIANA 811 Know what's below. Call before you dig.

NO.	DATE	DESCRIPTION
8	05-04-24	REVISED PER CITIZENS WATER COMMENTS
7	02-23-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
4	11-27-23	REVISED PER CITIZENS WATER COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY AND CITIZENS COMMENTS
1	09-15-23	REVISED PER CITY AND CITIZENS COMMENTS

NO.	DATE	DESCRIPTION
6	02-09-24	REVISED PER CITY COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
4	11-27-23	REVISED PER CITIZENS WATER COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY AND CITIZENS COMMENTS
1	09-15-23	REVISED PER CITY AND CITIZENS COMMENTS

NOTES:



1. ALL ELEVATIONS SHOWN DEPICT FINISHED GRADE UNLESS OTHERWISE NOTED. SUBTRACT FINISHES OR PAVEMENT SECTION TO ESTABLISH SUBGRADE ELEVATIONS.
2. ALL DIMENSIONS SHOWN ARE TO EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
3. ALL CURB AND GUTTER SHALL BE COMBINED CURB AND GUTTER PER INDOT STANDARD DRAWING NO. E 605-C000-01 UNLESS OTHERWISE NOTED.
4. ALL FUTURE LAND DISTURBANCE ON MONTANA LOT MUST DRAIN TO SOUTHWEST BASIN FOR WATER QUALITY AND DETENTION REQUIREMENTS.
5. ALL FUTURE SUBSTANTIAL IMPROVEMENTS TO THE MONTANA LOT, INCLUDING THE ADDITION OF NEW STORM DRAINS, SHALL HAVE AT LEAST 10 FEET OF HORIZONTAL SEPARATION AND 2 FEET OF VERTICAL SEPARATION FROM THE LOWEST GROUND ELEVATION NEXT TO A STRUCTURE TO THE 100-YEAR HIGH WATER ELEVATION. THEY MUST ALSO HAVE A LOWEST ELEVATION A MINIMUM OF 2 FEET ABOVE THE BASE FLOOD ELEVATION. MINIMUM FLOOD PROTECTION GRADES (MFPG) ARE PROVIDED ON EACH LOT SHOWN BELOW.
6. THE BASE FLOOD ELEVATION VARIES ALONG THE LENGTH OF THIS PROJECT AND ELEVATIONS ARE PROVIDED BELOW, BASED ON THE MARION COUNTY, INDIANA FLOOD INSURANCE STUDY DATED APRIL 16TH, 2016.
7. ALL ROOF DRAINS AND DOWNSPOUTS FOR FUTURE HOMES CONSTRUCTED ON LOTS SHALL BE DIRECTED TO THE FRONT YARDS AND INTO OR THROUGH THE STORM CONVEYANCE SYSTEMS. ALL ROOF SURFACES SHALL BE ROUTED THROUGH THE STORMWATER BMP AND DETENTION BASIN AT THE SOUTHWEST CORNER OF THE PROJECT SITE.



PROJECT NO.	220851 S04
PROJECT MANAGER:	JOR
DESIGNED BY:	MRV
DRAWN BY:	MRV
INDIANA	
THE RIDGE ON WILLIAMS CREEK	
INDIANAPOLIS	
619 N Pennsylvania Street Indianapolis, IN 46204 317.423.0890 www.v3co.com	
DRAWING NO. C3.3	

GRADING & SITE DEVELOPMENT PLAN

THE RIDGE ON WILLIAMS CREEK



MATCHLINE - SEE SHEET C3.1

MATCHLINE - SEE SHEET C3.4

A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
By: JN

INDIANA811
 Know what's below.
 Call before you dig.

LEGEND
 NATURALIZED TRAIL


MATCHLINE - SEE SHEET C3.3

MATCHLINE - SEE SHEET C3.2

COLORADO LOT
59,721 SF
1.371 AC
MFPG FRONT = 815.08
MFPG BACK = 791.36

UTAH LOT
60,395 SF
1.386 AC
MFPG FRONT = 810.20
MFPG BACK = 795.75

COMMON AREA LOT
85,111 SF
1.9 AC



NOTES:



1. ALL ELEVATIONS SHOWN DEPICT FINISHED GRADE UNLESS OTHERWISE NOTED. SUBTRACT TOPSOIL THICKNESS OR PAVEMENT SECTION TO ESTABLISH SUBGRADE ELEVATIONS.
2. ALL DIMENSIONS SHOWN ARE TO EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
3. ALL CURB AND GUTTER SHALL BE COMBINED CURB AND GUTTER PER INDOT STANDARD DRAWING NO. E 605-CCCG-01 UNLESS OTHERWISE NOTED.
4. ALL FUTURE LAND DISTURBANCE ON COLORADO AND UTAH LOTS MUST DRAIN TO SOUTHWEST BASIN FOR WATER QUALITY AND DETENTION REQUIREMENTS.
5. ALL FUTURE SUBSTANTIAL IMPROVEMENTS TO THE COLORADO AND UTAH LOTS, INCLUDING THE ADDITION OF NEW STRUCTURES, SHALL HAVE AT LEAST 10 FEET OF HORIZONTAL SEPARATION AND 2 FEET OF VERTICAL SEPARATION FROM THE LOWEST GROUND ELEVATION NEXT TO A STRUCTURE TO THE 100-YEAR HIGH WATER ELEVATION. THEY MUST ALSO HAVE A LOWEST ELEVATION A MINIMUM OF 2 FEET ABOVE THE BASE FLOOD ELEVATION. MINIMUM FLOOD PROTECTION GRADES (MFPG) ARE PROVIDED ON EACH LOT SHOWN ABOVE.
6. THE BASE FLOOD ELEVATION VARIES ALONG THE LENGTH OF THIS PROJECT AND ELEVATIONS ARE PROVIDED ABOVE. BASED ON THE MARION COUNTY, INDIANA FLOOD INSURANCE STUDY, DATED APRIL 16TH, 2016.
7. ALL ROOF DRAINS AND DOWNSPOUTS FOR FUTURE HOMES CONSTRUCTED ON LOTS SHALL BE DIRECTED TO THE FRONT YARDS AND INTO OR THROUGH THE STORM CONVEYANCE SYSTEMS. ALL ROOF SURFACES SHALL BE ROUTED THROUGH THE STORMWATER BMP AND DETENTION BASIN AT THE SOUTHWEST CORNER OF THE PROJECT SITE.



A202400023641

03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
By: JN

LEGEND
NATURALIZED TRAIL



KEY MAP
N.T.S.

DRAWING NO.
C3.4

619 N Parmsylvania Street
Indianapolis, IN 46204
www.v3co.com
317.423.0690





GRADING & SITE DEVELOPMENT
PLAN
THE RIDGE ON WILLIAMS CREEK
INDIANA

NO.	DATE	DESCRIPTION
1	09-15-23	REVISED PER CITY ANTI-CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY ANTI-CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY ANTI-CITIZENS COMMENTS
4	11-27-23	REVISED PER CITY ANTI-CITIZENS COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

NO.	DATE	DESCRIPTION
7	02-23-24	REVISED PER CITY COMMENTS
8	03-04-24	REVISED PER CITY COMMENTS

PROJECT NO.:	220861 S04
PROJECT MANAGER:	JOR
DESIGNED BY:	MRV
DRAWN BY:	MRV
INDIANA	

ORIGINAL ISSUE DATE:	07-07-2023
----------------------	------------



A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
Fee: \$ 140.00
PAGES: 60
By: JN

INDIANA 811
 Know what's below.
 Call before you dig.

EROSION CONTROL PLAN
THE RIDGE ON WILLIAMS CREEK
INDIANAPOLIS

REVISIONS	
NO.	DATE
1	09-16-23
2	10-18-23
3	11-15-23
4	11-27-23
5	01-08-24
6	02-09-24

PROJECT NO.: 220851 S04
 ORIGINAL ISSUE DATE: 07-07-2023

DESIGNED BY: MRY
 DRAWN BY: MRY

JOR
 PROJECT MANAGER

619 N Pennsylvania Street
 Indianapolis, IN 46204
 www.v3co.com

DRAWING NO.
C4.5

LEGEND

- PROPOSED SILT FENCE, SEE SHEET C4.11
- CONSTRUCTION STAGING/STOCKPILE AREAS
- PROPOSED YARD INLET PROTECTION SEE SHEET C4.10
- PROPOSED PAVEMENT INLET PROTECTION SEE SHEET C4.11
- EROSION CONTROL BLANKET, SEE SHEET C4.10
- PERMANENT SEEDING AREA, SEE SHEET C4.11 FOR MIXTURE
- TREE PROTECTION FENCING, SEE SHEET C4.10 FOR DETAILS
- RIP RAP AT END SECTIONS, SEE SHEET C4.11 FOR DETAILS

NOTES:

- NO EARTH DISTURBING ACTIVITIES MAY TAKE PLACE WITHOUT AN APPROVED STORM WATER MANAGEMENT PERMIT.
- ALL DISCHARGE OF CONTAMINATED WATER DUE TO DEWATERING SHALL OUTLET THROUGH EXISTING VEGETATION OR FILTER BAGS THAT WILL NOT ADVERSELY IMPACT STORM WATER QUALITY.
- ANY AREAS DISTURBED DUE TO CONSTRUCTION SHALL BE RE-SEEDING WITH TURF UNLESS NOTED OTHERWISE ON THE PLANS. SEE EROSION CONTROL DETAILS FOR SEED MIXES.
- ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED IN THE FIELD BY THE INSPECTOR.
- IF SITE REMAINS INACTIVE FOR A PERIOD OF 2 WEEKS, THEN STABILIZATION IS REQUIRED TO TAKE PLACE IN THE FORM OF TEMPORARY SEEDING, MULCH, OR SPRAY ON POLYMER.

6. EROSION CONTROL BLANKET IS REQUIRED FOR ALL SLOPES 3:1 OR GREATER.

7. PORTABLE TOILETS MUST BE ANCHORED TO PREVENT SPILLS.

8. THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE CITY OF WESTFIELD PRIOR TO ANY CONSTRUCTION ON THE SITE BEING STARTED. ALL CONSTRUCTION SEQUENCING SHALL BE AGREED UPON PRIOR TO THE START OF CONSTRUCTION.

9. THE CONTRACTOR AND/OR DEVELOPER SHALL NOTIFY IDEM AND THE CITY OF WESTFIELD 48 HOURS PRIOR TO START OF CONSTRUCTION.

10. THE CITY OF INDIANAPOLIS RESERVES THE RIGHT TO REQUIRE ADDITIONAL ON SITE CONTROLS AS DEEMED NECESSARY TO MAINTAIN COMPLIANCE WITH THE CITY'S STORM WATER MANAGEMENT ORDINANCE. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE INDIANAPOLIS STORM WATER QUALITY MANUAL.

11. PUBLIC AND PRIVATE ROADWAYS SHALL BE KEPT CLEARED OF ACCUMULATED SEDIMENT. BULK CLEARING OF ACCUMULATED SEDIMENT SHALL NOT INCLUDE FLUSHING THE AREA WITH WATER. PROJECTS SUBJECT TO IDEM'S CSGP SHALL REMOVE SEDIMENT FROM PUBLIC RIGHTS-OF-WAY NOT EXCLUSIVE OF CONSTRUCTION TRAFFIC AT THE END OF EACH DAY PER THE CSGP REQUIREMENTS.

12. ALL PROPOSED EROSION AND SEDIMENT CONTROL SHALL BE IN CONFORMANCE WITH CHAPTER 600 OF THE CITY OF INDIANAPOLIS STORM WATER SPECIFICATIONS MANUAL, LATEST EDITION. DISCREPANCIES BETWEEN THE PLANS AND THE MANUAL SHALL NOT ALLEVIATE THE CONTRACTOR FROM ADHERING TO THE REQUIREMENTS AS SET FORTH IN THE MANUAL.

13. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED BY THE INSPECTOR.


MATCHLINE - SEE SHEET C4.6

MATCHLINE - SEE BELOW

MATCHLINE - SEE SHEET C4.5

CALIFORNIA LOT
56,791 SF
1,304 AC
MFPG = 805.83

OREGON LOT
54,564 SF
1,253 AC
MFPG FRONT = 815.08
MFPG BACK = 804.59



NO.	DATE	DESCRIPTION
1	09-15-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY AND CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
4	11-27-23	REVISED PER CITY AND CITIZENS COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

INDIANAPOLIS

THE RIDGE ON WILLIAMS CREEK

EROSION CONTROL PLAN

PROJECT NO.: 220851 S04
 PROJECT MANAGER: JOR
 DESIGNED BY: MRV
 DRAWN BY: MRV

INDIANA

619 N Pennsylvania Street
 Indianapolis, IN 46204
 317.423.0690
 www.v3co.com

C4.6

DRAWING NO.

CURB INLET
 TC 802.59
 15' RCP W/ INV. 756.50
 12' RCP E. INV. 756.34

03/28/2024 10:58 AM
 FAITH KIMBROUGH
 MARION COUNTY IN RECORDER
 PAGES: 60
 BY: JN
 FEE: \$ 140.00

A202400023641

MATCHLINE - SEE SHEET C4.8

GRAPHIC SCALE
 1" = 20'

- NOTES:**
- NO EARTH DISTURBING ACTIVITIES MAY TAKE PLACE WITHOUT AN APPROVED STORM WATER MANAGEMENT PERMIT.
 - ALL DISCHARGE OF CONTAMINATED WATER DUE TO DEWATERING SHALL OUTLET THROUGH EXISTING VEGETATION OR FILTER BAGS THAT WILL NOT ADVERSELY IMPACT STORM WATER QUALITY.
 - ANY AREAS DISTURBED DUE TO CONSTRUCTION SHALL BE RE-SEED WITH TURF UNLESS NOTED OTHERWISE ON THE PLANS. SEE EROSION CONTROL DETAILS FOR SEED MIXES.
 - ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED IN THE FIELD BY THE INSPECTOR.
 - IF SITE REMAINS INACTIVE FOR A PERIOD OF 2 WEEKS, THEN STABILIZATION IS REQUIRED TO TAKE PLACE IN THE FORM OF TEMPORARY SEEDING, MULCH, OR SPRAY ON POLYMER.

- EROSION CONTROL BLANKET IS REQUIRED FOR ALL SLOPES 3:1 OR GREATER.
- PORTABLE TOILETS MUST BE ANCHORED TO PREVENT SPILLS.
- THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE CITY OF WESTFIELD PRIOR TO ANY CONSTRUCTING ON THE SITE BEING STARTED. ALL CONSTRUCTION SEQUENCING SHALL BE AGREED UPON PRIOR TO THE START OF CONSTRUCTION.
- THE CONTRACTOR AND/OR DEVELOPER SHALL NOTIFY IDEM AND THE CITY OF WESTFIELD 48 HOURS PRIOR TO START OF CONSTRUCTION.
- THE CITY OF INDIANAPOLIS RESERVES THE RIGHT TO REQUIRE ADDITIONAL ON-SITE CONTROLS AS DEEMED NECESSARY TO MAINTAIN COMPLIANCE WITH THE CITY'S STORMWATER MANAGEMENT ORDINANCE. ALL EROSION AND SEDIMENT PREVENTION, BEST MANAGEMENT PRACTICES AND POLLUTION PREVENTION MEASURES MUST BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE INDIANA STORMWATER QUALITY MANUAL.

- EROSION CONTROL BLANKET.**
SEE SHEET C4.10
- PERMANENT SEEDING AREA.**
SEE SHEET C4.11 FOR MIXTURE
- TREE PROTECTION FENCING.**
SEE SHEET C4.10 FOR DETAILS
- RIP RAP AT END SECTIONS.**
SEE SHEET C4.11 FOR DETAILS

- PROPOSED SILT FENCE.**
SEE SHEET C4.11
- CONSTRUCTION STAGING/STOCKPILE AREAS**
- PROPOSED YARD INLET PROTECTION**
SEE SHEET C4.10
- PROPOSED PAVEMENT INLET PROTECTION**
SEE SHEET C4.11
- PROPOSED CHECK DAM**
SEE SHEET C4.10 FOR DETAILS

LEGEND

KEY MAP
M.T.S.

11. PUBLIC AND PRIVATE ROADWAYS SHALL BE KEPT CLEARED OF ACCUMULATED SEDIMENT. BULK CLEANING OF ACCUMULATED SEDIMENT SHALL NOT INCLUDE FLUSHING THE AREA. PROJECTS SUBJECT TO IDEM'S CSGP SHALL REMOVE SEDIMENT FROM PUBLIC RIGHTS-OF-WAY NOT EXCLUSIVE OF CONSTRUCTION TRAFFIC AT THE END OF EACH DAY PER THE CSGP REQUIREMENTS.

12. ALL PROPOSED EROSION AND SEDIMENT CONTROL SHALL BE IN CONFORMANCE WITH CHAPTER 600 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL, LATEST EDITION. DISCREPANCIES BETWEEN THE PLANS AND THE MANUAL SHALL NOT ALLEVIATE THE CONTRACTOR FROM ADHERING TO THE REQUIREMENTS AS SET FORTH IN THE MANUAL.

13. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED BY THE INSPECTOR.


MATCHLINE - SEE SHEET C4.6

MATCHLINE - SEE SHEET C4.8

MATCHLINE - SEE SHEET C4.9

WASHINGTON LOT

60,395 SF
1.386 AC
MFPG FRONT = 815.08
MFPG BACK = 797.04



NOTES:


- NO EARTH DISTURBING ACTIVITIES MAY TAKE PLACE WITHOUT AN APPROVED STORM WATER MANAGEMENT PERMIT.
- ALL DISCHARGE OF CONTAMINATED WATER DUE TO DEWATERING SHALL OUTLET THROUGH EXISTING VEGETATION OR FILTER BAGS THAT WILL NOT ADVERSELY IMPACT STORM WATER QUALITY.
- ANY AREAS DISTURBED DUE TO CONSTRUCTION SHALL BE RE-SEED WITH TURF UNLESS NOTED OTHERWISE ON THE PLANS. SEE EROSION CONTROL DETAILS FOR SEED MIXES.
- ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED IN THE FIELD BY THE INSPECTOR.
- IF SITE REMAINS INACTIVE FOR A PERIOD OF 2 WEEKS, THEN STABILIZATION IS REQUIRED TO TAKE PLACE IN THE FORM OF TEMPORARY SEEDING, MULCH, OR SPRAY ON POLYMER.
- EROSION CONTROL BLANKET IS REQUIRED FOR ALL SLOPES 3:1 OR GREATER.
- PORTABLE TOILETS MUST BE ANCHORED TO PREVENT SPILLS.
- THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE CITY OF WESTFIELD PRIOR TO ANY CONSTRUCTION ON THE SITE BEING STARTED. ALL CONSTRUCTION SEQUENCING SHALL BE AGREED UPON PRIOR TO THE START OF CONSTRUCTION.
- THE CONTRACTOR AND/OR DEVELOPER SHALL NOTIFY IDEM AND THE CITY OF WESTFIELD 48 HOURS PRIOR TO START OF CONSTRUCTION.
- THE CITY OF INDIANAPOLIS RESERVES THE RIGHT TO REQUIRE ADDITIONAL ON-SITE CONTROLS AS DEEMED NECESSARY TO MAINTAIN COMPLIANCE WITH THE CITY'S STORMWATER MANAGEMENT ORDINANCE. ALL EROSION AND SEDIMENT CONTROLS, BEST MANAGEMENT PRACTICES AND POLLUTION PREVENTION MEASURES MUST BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE INDIANA STORMWATER QUALITY MANUAL.

- EROSION CONTROL BLANKET, SEE SHEET C4.10
- PERMANENT SEEDING AREA, SEE SHEET C4.11 FOR MIXTURE
- TREE PROTECTION FENCING, SEE SHEET C4.10 FOR DETAILS
- RIP RAP AT END SECTIONS, SEE SHEET C4.11 FOR DETAILS

- CONSTRUCTION STAGING/STOCKPILE AREAS
- PROPOSED YARD INLET PROTECTION SEE SHEET C4.10
- PROPOSED PAVEMENT INLET PROTECTION SEE SHEET C4.11
- PROPOSED CHECK DAM SEE SHEET C4.10 FOR DETAILS


- PROPOSED SILT FENCE, SEE SHEET C4.11

LEGEND



03/28/2024 10:58 AM
 FAITH KIMBROUGH
 MARION COUNTY IN RECORDER
 FEE: \$ 140.00
 PAGES: 60
 BY: JN

A202400023641



- PUBLIC AND PRIVATE ROADWAYS SHALL BE KEPT CLEARED OF ACCUMULATED SEDIMENT. BULK CLEARING OF ACCUMULATED SEDIMENT SHALL NOT INCLUDE FLUSHING THE AREA WITH WATER. PROJECTS SUBJECT TO IDEM'S CSGP SHALL REMOVE SEDIMENT FROM PUBLIC RIGHTS-OF-WAY NOT EXCLUSIVE OF CONSTRUCTION TRAFFIC AT THE END OF EACH DAY PER THE CSGP REQUIREMENTS.
- ALL PROPOSED EROSION AND SEDIMENT CONTROL SHALL BE IN CONFORMANCE WITH CHAPTER 600 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL, LATEST EDITION. DISCREPANCIES BETWEEN THE PLANS AND THE MANUAL SHALL NOT ALLEVIATE THE CONTRACTOR FROM ADHERING TO THE REQUIREMENTS AS SET FORTH IN THE MANUAL.
- ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED BY THE INSPECTOR.

NO.	DATE	DESCRIPTION
1	09-16-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITIZENS COMMENTS
3	11-16-23	REVISED PER CITY AND CITIZENS COMMENTS
4	11-27-23	REVISED PER CITIZENS WATER COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

PROJECT NO: 220851 S04
 PROJECT MANAGER: JOR
 DESIGNED BY: MRY
 DRAWN BY: MRY
 ORIGINAL ISSUE DATE: 07-07-2023

INDIANAPOLIS
 THE RIDGE ON WILLIAMS CREEK
 EROSION CONTROL PLAN

INDIANAPOLIS
 619 N Pennsylvania Street
 Indianapolis, IN 46204
 www.a3c0.com

C4.7
 DRAWING NO.

MATCHLINE - SEE SHEET C4.6

MATCHLINE - SEE SHEET C4.7

MONTANA LOT
 110,583 SF
 2.539 AC
 MFPG = 815.08





LEGEND

	PROPOSED SILT FENCE, SEE SHEET C4.11
	EROSION CONTROL BLANKET, SEE SHEET C4.10
	RIP RAP AT END SECTIONS, SEE SHEET C4.11 FOR DETAILS

- NOTES:**
- NO EARTH DISTURBING ACTIVITIES MAY TAKE PLACE WITHOUT AN APPROVED STORM WATER MANAGEMENT PERMIT.
 - ALL DISCHARGE OF CONTAMINATED WATER DUE TO DEWATERING SHALL OUTLET THROUGH EXISTING VEGETATION OR FILTER BAGS THAT WILL NOT ADVERSELY IMPACT STORM WATER QUALITY.
 - ANY AREAS DISTURBED DUE TO CONSTRUCTION SHALL BE RE-SEEDED WITH TURF UNLESS NOTED OTHERWISE ON THE PLANS. SEE EROSION CONTROL DETAILS FOR SEED MIXES.
 - ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED IN THE FIELD BY THE INSPECTOR.
 - IF SITE REMAINS INACTIVE FOR A PERIOD OF 2 WEEKS, THEN STABILIZATION IS REQUIRED TO TAKE PLACE IN THE FORM OF TEMPORARY SEEDING, MULCH, OR SPRAY ON POLYMER.

- EROSION CONTROL BLANKET IS REQUIRED FOR ALL SLOPES 3:1 OR GREATER.
- PORTABLE TOILETS MUST BE ANCHORED TO PREVENT SPILLS.
- THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE CITY OF INDIANAPOLIS PRIOR TO ANY CONSTRUCTION ON THE SITE BEING STARTED. ALL CONSTRUCTION SEQUENCING SHALL BE AGREED UPON PRIOR TO THE START OF CONSTRUCTION.
- THE CONTRACTOR AND/OR DEVELOPER SHALL NOTIFY IDEM AND THE CITY OF INDIANAPOLIS 48 HOURS PRIOR TO START OF CONSTRUCTION.
- THE CITY OF INDIANAPOLIS RESERVES THE RIGHT TO REQUIRE ADDITIONAL ON-SITE CONTROLS AS DEEMED NECESSARY TO MAINTAIN COMPLIANCE WITH THE CITY'S STORMWATER MANAGEMENT ORDINANCE. ALL EROSION AND SEDIMENT CONTROLS, BEST MANAGEMENT PRACTICES AND POLLUTION PREVENTION MEASURES MUST BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE INDIANA STORMWATER QUALITY MANUAL.

- PUBLIC AND PRIVATE ROADWAYS SHALL BE KEPT CLEARED OF ACCUMULATED SEDIMENT. BULK CLEARING OF ACCUMULATED SEDIMENT SHALL NOT INCLUDE FLUSHING THE AREA WITH WATER. PROJECTS SUBJECT TO IDEM'S CSQP SHALL REMOVE SEDIMENT FROM PUBLIC RIGHTS-OF-WAY NOT EXCLUSIVE OF CONSTRUCTION TRAFFIC AT THE END OF EACH DAY PER THE CSQP REQUIREMENTS.
- ALL PROPOSED EROSION AND SEDIMENT CONTROL SHALL BE IN CONFORMANCE WITH CHAPTER 600 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL, LATEST EDITION. DISCREPANCIES BETWEEN THE PLANS AND THE MANUAL SHALL NOT ALLEVIATE THE CONTRACTOR FROM ADHERING TO THE REQUIREMENTS AS SET FORTH IN THE MANUAL.
- ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED BY THE INSPECTOR.



C4.8

DRAWING NO.

619 N Pennsylvania Street
 Indianapolis, IN 46204
 317.423.0690
 www.v360.com

INDIANAPOLIS
THE RIDGE ON WILLIAMS CREEK
EROSION CONTROL PLAN

PROJECT NO: 220851 S04
 ORIGINAL ISSUE DATE: 07-07-2023

NO.	DATE	DESCRIPTION
1	09-16-23	REVISED PER CITY AN CITIZENS COMMENTS
2	10-18-23	REVISED PER CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY AN CITIZENS COMMENTS
4	11-27-23	REVISED PER CITIZEN WATER COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

DESIGNED BY: MRV
 DRAWN BY: MRV

PROJECT MANAGER: JOR
 PROJECT NO: 220851 S04

INDIANAPOLIS


MATCHLINE - SEE SHEET C4.8

MATCHLINE - SEE SHEET C4.7

COLORADO LOT
59,721 SF
1.371 AC
MFPG FRONT = 815.08
MFPG BACK = 791.36

UTAH LOT
60,395 SF
1.386 AC
MFPG FRONT = 810.20
MFPG BACK = 795.75

COMMON AREA LOT
85,471 SF
1.962 AC



REVISIONS	
NO.	DATE
1	09-15-23
2	10-18-23
3	11-15-23
4	11-27-23
5	01-08-24
6	02-09-24

PROJECT NO. 220851 S04	INDIANAPOLIS
PROJECT MANAGER: JOR	THE RIDGE ON WILLIAMS CREEK
DESIGNED BY: MRV	EROSION CONTROL PLAN
DRAWN BY: MRV	INDIANAPOLIS
ORIGINAL ISSUE DATE: 07-07-2023	

619 N Pennsylvania Street
Indianapolis, IN 46204
317.423.0690
www.v360.com

DRAWING NO. **C4.9**

GRAPHIC SCALE
1" = 20'

KEY MAP
N.T.S.

Indiana 80
Home starts before you call before you dig.

11. PUBLIC AND PRIVATE ROADWAYS SHALL BE KEPT CLEARED OF ACCUMULATED SEDIMENT. BULK CLEARING OF ACCUMULATED SEDIMENT SHALL NOT INCLUDE FLUSHING THE AREA WITH WATER. PROJECTS SUBJECT TO IDEM'S CSQP SHALL REMOVE SEDIMENT FROM PUBLIC RIGHTS-OF-WAY NOT EXCLUSIVE OF CONSTRUCTION TRAFFIC AT THE END OF EACH DAY PER THE CSQP REQUIREMENTS.
12. ALL PROPOSED EROSION AND SEDIMENT CONTROL SHALL BE IN CONFORMANCE WITH CHAPTER 600 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL, LATEST EDITION. DISCREPANCIES BETWEEN THE PLANS AND THE MANUAL SHALL NOT ALLOW THE CONTRACTOR FROM ADHERING TO THE REQUIREMENTS AS SET FORTH IN THE MANUAL.
13. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED BY THE INSPECTOR.

6. EROSION CONTROL BLANKET IS REQUIRED FOR ALL SLOPES 3:1 OR GREATER.
7. PORTABLE TOILETS MUST BE ANCHORED TO PREVENT SPILLS.
8. THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE CITY OF WESTFIELD PRIOR TO ANY CONSTRUCTION ON THE SITE BEING STARTED. ALL CONSTRUCTION SEQUENCING SHALL BE AGREED UPON PRIOR TO THE START OF CONSTRUCTION.
9. THE CONTRACTOR AND/OR DEVELOPER SHALL NOTIFY IDEM AND THE CITY OF WESTFIELD 48 HOURS PRIOR TO START OF CONSTRUCTION.
10. THE CITY OF INDIANAPOLIS RESERVES THE RIGHT TO REQUIRE ADDITIONAL ON-SITE CONTROLS AS DEEMED NECESSARY TO MAINTAIN COMPLIANCE WITH THE CITY'S STORMWATER MANAGEMENT ORDINANCE. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE INDIANA STORMWATER QUALITY MANUAL.

- NOTES:
1. NO EARTH DISTURBING ACTIVITIES MAY TAKE PLACE WITHOUT AN APPROVED STORM WATER MANAGEMENT PERMIT.
 2. ALL DISCHARGE OF CONTAMINATED WATER DUE TO DEWATERING SHALL OUTLET THROUGH EXISTING VEGETATION OR FILTER BAGS THAT WILL NOT ADVERSELY IMPACT STORM WATER QUALITY.
 3. ANY AREAS DISTURBED DUE TO CONSTRUCTION SHALL BE RE-SEEDDED WITH TURF UNLESS NOTED OTHERWISE ON THE PLANS. SEE EROSION CONTROL DETAILS FOR SEED MIXES.
 4. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED IN THE FIELD BY THE INSPECTOR.
 5. IF SITE REMAINS INACTIVE FOR A PERIOD OF 2 WEEKS, THEN STABILIZATION IS REQUIRED TO TAKE PLACE IN THE FORM OF TEMPORARY SEEDING, MULCH, OR SPRAY ON POLYMER.

LEGEND

- PROPOSED SILT FENCE, SEE SHEET C4.11
- EROSION CONTROL BLANKET, SEE SHEET C4.10
- RIP RAP AT END SECTIONS, SEE SHEET C4.11 FOR DETAILS


FAITH KIMROD
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
BY: JM

A202400023641
03/28/2024 10:58 AM





NO.	DATE	DESCRIPTION
1	10-15-23	REVISED PER CITY COMMENTS
2	10-18-23	REVISED PER CITY COMMENTS
3	11-18-23	REVISED PER CITY COMMENTS
4	11-27-23	REVISED PER CITY COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

INDIANAPOLIS
EROSION CONTROL DETAILS
THE RIDGE ON WILLIAMS CREEK
 DRAWN BY: MRV
 DESIGNED BY: MRV
 PROJECT MANAGER: JOR
 PROJECT NO.: 220851 S04
 ORIGINAL ISSUE DATE: 07-07-2023

619 Pennsylvania Street
 Indianapolis, IN 46204
 317.423.0690
 www.v3co.com



C4.10
 DRAWING NO.



Temporary Construction Entrance
 Dimensions:
 • Width - 20 feet minimum or full width of entrance/road roadway, whichever is greater.
 • Length - 150 feet minimum (length can be shorter for small sites).
 • Curb - 2" wide curb (minimum 12" high).
 • Level area with three inch, or larger, washed aggregate or install a commercial wash rock.
 • Direct waste water to a sediment trap or basin.

Installation:
 1. Remove all vegetation and other objectionable material from the foundation area.
 2. Grade foundation and crown for positive drainage. If the slope of the construction entrance is toward a public road, the entrance shall be a minimum of 12" above the finished ground level.
 3. Install a curb pipe under the pad if needed to maintain proper public road drainage.
 4. If wet conditions are anticipated, place geotextile fabric on the graded foundation to improve stability.
 5. Place aggregate on top of the geotextile fabric to the dimensions and grade shown in the construction plans, leaving the surface smooth and sloped for drainage.

Maintenance:
 • Inspect daily.
 • Top dress with clean aggregate as needed.
 • Immediately remove mud and sediment located or washed onto public roads.
 • Flushing should only be used if the water can be conveyed into a sediment trap or basin.

Tree Protection Fence
 NOTES:
 1. EITHER PLASTIC OR WOOD ORANGE SHAW FENCING OF 4 FOOT HEIGHT SHALL BE INSTALLED AT THE PERIMETER OF THE PROTECTED AREA.
 2. STAKES SHALL BE 5 METERS, 16 FEET SPACED AND FURTHER APART THAN 4' ON CENTER.
 3. FENCING SHALL NOT BE INSTALLED CLOSER TO THE TREE THAN THE DROP LINE OF THOSE TREES TO BE PROTECTED.
 4. APPROVAL FROM THE CITY.
 5. UNDER NO CIRCUMSTANCES SHALL THE PROTECTIVE FENCING BE REMOVED WITHOUT PROPER APPROVAL FROM THE CITY.
 6. NO PERSON SHALL CONDUCT ANY ACTIVITY WITHIN THE AREAS PROPOSED TO REMAIN. THIS INCLUDES BUT IS NOT LIMITED TO:
 6.1. SHEDS OR BUILDINGS OR CHANGING WITHIN THE PROTECTED AREAS.
 6.2. NO BUILDING MATERIALS OR CONSTRUCTION EQUIPMENT WITHIN THE PROTECTED AREAS.
 6.3. NO STORAGE OF MATERIALS OR EQUIPMENT WITHIN THE PROTECTED AREAS.
 6.4. NO REMOVAL OF VEGETATION WITHIN THE PROTECTED AREAS.
 6.5. NO STORAGE OF MATERIALS OR EQUIPMENT WITHIN THE PROTECTED AREAS.
 6.6. INSTANCES WHERE SWALES ARE APPROVED THROUGH A PROTECTED AREA, THE SWALES SHALL BE HAND DUG. MACHINERY OF ANY KIND IS PROHIBITED.
 7. REGULATED WOODLANDS OR REGULATED TREES ADJACENT TO THE PROPERTY ARE ALSO REQUIRED TO BE PROTECTED.

Turf Reinforcement Mat Detail
 NOT TO SCALE



Silt Fence
 NOT TO SCALE

Tree Protection Fence
 NOT TO SCALE

Welded Wire Monofilament Yard Inlet Protection
 NOT TO SCALE

Native Planting Area
 DO NOT MOW
 DO NOT SPRAY

BMP Signage Detail
 NOT TO SCALE



Concrete Washout Container
 VINYL-CON™ PORTABLE CONCRETE WASHOUT CONTAINER
 VINYL-CON™ DETAIL A.2
 NOT TO SCALE

Check Dam
 NOT TO SCALE

Channel Lining
 NOT TO SCALE

Concrete Washout System Specifications
 Vinyl-Con™ system utilizes a portable, self-contained and walk-behind container with filter bag system and Aqua-Solution™ to control, capture and contain concrete washwater and prevent runoff.

Site Management
 • Complete installation of the system and have washout locations operational prior to concrete delivery.
 • Do not wash out into storm drains, wetlands, streams, rivers, creeks, ditches, or streets.
 • Never wash out into a storm sewer drainage system. These systems are typically connected to a natural conveyance system.
 • If necessary, provide stable ingress and egress.
 • Do not back flush equipment at the project site. Back flushing should be restricted to the plant as it generates large volumes of waste that may exceed the capacity of the washout systems. If an emergency arises, back flush should only be performed with the permission of the on-site manager for the project.

Location
 • Locate concrete washout systems at least 50 feet from any creeks, wetlands, ditches, kerst features, or storm drains/minor conveyance systems.
 • Locate concrete washout systems in relatively flat areas that have established vegetation and do not receive runoff from adjacent land areas.
 • Locate in areas that provide easy access for concrete trucks and other construction equipment.
 • Locate away from other construction traffic to reduce the potential for damage to the system.

Vinyl-Con Container
 1. Locate the washout in an area that is free of rocks and other debris that may cause tears or punctures in the Vinyl-Con Container.
 2. Spread the Vinyl-Con™ mat on the ground with the opening facing up.
 3. Lay out the framework pieces on the ground as follows:
 3a. 6x8 Vinyl-Con™ (4) 4-way corner fittings; (4) 7' upright fittings; (2) couples; (4) 18' legs; (2) 47" wets; (2) 35.5" wets
 4. Assemble:
 • Insert 47" wet into 4' pocket of Vinyl-Con™ (repeat on opposite side)
 • Attach (2) 35.5" wets together with (1) couple (repeat on opposite side)
 • Insert the wet with couple into 6' pocket of Vinyl-Con™ (repeat on opposite side)
 • Connect (4) 4-way corners to the wets
 • Connect (4) 7' uprights to the wets
 • Insert 7' upright into the top of the 4-way on each corner (for use of filter bags)
 5. Loops are available on each corner to secure the Vinyl-Con™ to the ground with stakes in high wind areas. Once the concrete is in the Vinyl-Con™ there is no need for stakes.

Install Filter Bag
 1. Spread the Vinyl-Con™ Filter Bag flat inside the Vinyl-Con™ container.
 2. Insert the 7' per upright into the top of the corner fittings on the Vinyl-Con™ container.
 3. Place the filter bag corner loops over the Vinyl-Con™ uprights. Be sure to twist the loops several times and then connect the corner pre-attached to the Vinyl-Con™ uprights.
 4. Begin pouring concrete washout into the filter bag.
 5. When the filter bag is full of concrete, lift the bag with the straps allowing the water to permeate through the bag and into the Vinyl-Con™ container.
 6. Set the filter bag aside and refill the Vinyl-Con™ container with another filter bag.

Maintenance
 • Place a cover over the washout facility prior to a predicted rainfall event to prevent accumulation of water and possible overflow of the system.
 • Inspect daily and after each storm event.
 • Inspect the integrity of overall structure including the replacement system.
 • Check for any debris or obstructions that may block the flow of water.
 • Once filter bag is full of hardened washout material, remove for recycling.
 • Place another filter bag inside the Vinyl-Con™ container and repeat step #1 over again multiple times.
 • Once Vinyl-Con™ container is full of cementitious washwater, place last filter bag inside to allow washwater to permeate through the filter bag and broadcast Aqua-Solution™ into washwater turning the washwater into a gelled content in about 5 minutes.
 • Once entire filter bag of washwater is a gelled content, remove for recycling.
 • Reuse Vinyl-Con™ washout container, begin with step #1 with more filter bags.

EROSION CONTROL DETAILS
THE RIDGE ON WILLIAMS CREEK

PROJECT NO: 220851 S04
 ORIGINAL ISSUE DATE: 07-07-2023

TEMPORARY SEEDING DATES

NO.	DATE	REVISIONS
1	09-16-23	REVISED PER CITY COMMENTS
2	10-18-23	REVISED PER CITY COMMENTS
3	11-16-23	REVISED PER CITY COMMENTS
4	11-27-23	REVISED PER CITY COMMENTS
5	10-09-24	REVISED PER CITY COMMENTS

PERMANENT SEEDING DATES

NO.	DATE	REVISIONS
1	02-22-24	REVISED PER CITY COMMENTS
2	03-04-24	REVISED PER CITY COMMENTS
3	03-04-24	REVISED PER CITY COMMENTS
4	03-04-24	REVISED PER CITY COMMENTS
5	03-04-24	REVISED PER CITY COMMENTS
6	03-04-24	REVISED PER CITY COMMENTS
7	03-04-24	REVISED PER CITY COMMENTS
8	03-04-24	REVISED PER CITY COMMENTS

SEEDING PREPARATION
 APPLY LIME TO RAISE THE PH TO THE LEVEL NEEDED FOR SPECIES BEING SEED. APPLY 23 POUNDS OF 12-12-12 ANALYSIS FERTILIZER (OR EQUIVALENT) PER 1000 SQ. FT. APPROXIMATELY 1000 POUNDS PER ACRE OR FERTILIZER ACCORDING TO LABEL DIRECTIONS. FERTILIZER SHOULD BE APPLIED IN ORGANIC MATTER AND FERTILITY WILL GREATLY ENHANCE VEGETATIVE GROWTH.
 WORK THE FERTILIZER AND LIME INTO THE SOIL TO A DEPTH OF 3-3 INCHES WITH A HARROW, DISK OR RAKE OPERATED ACROSS THE SLOPE AS MUCH AS POSSIBLE.
SEEDING
 SELECT A SEED MIXTURE BASED ON PROJECTED USE OF THE AREA (SEE PERMANENT SEED MIXTURE CHART). WHILE CONSIDERING BEST SEEDING DATES, UNTIL PERMANENT SEEDING CAN BE APPLIED. IF TOLERANCES ARE A PROBLEM, SUCH AS UNTIL TOLERANCE OF SEEDINGS ADJACENT TO STREETS AND HIGHWAYS, SEE SEED TOLERANCE CHART.

WET	NORM	DRY	SHADE	CLOSE MOISTURE	TOLERANCE	FERTILITY	WINTER	HARDNESS	FLOORING	TOLERANCE	MATURE	HEIGHT	EMERGENCE	SOIL	TOLERANCE
2	1	2	1	1	1	1	1	1	1	1	20-25	12-18	7-21	S	S
2	1	2	1	1	1	1	1	1	1	1	20-35	12-18	10-20	MT	MT
2	1	1	1	1	1	1	1	1	1	1	24-35	24-36	5-14	T	T
2	1	2	1	1	2	1	1	1	1	1	15-20	12-18	5-10	MT	MT
1	1	1	1	1	1	1	1	1	1	1	5-10	2-4	14-21	T	T
1	1	1	1	1	1	1	1	1	1	1	7-10	18	5-10	S	S

SEEDING TABLES AND INFORMATION

TYPE OF SEED	LBS/ACRE	REMARKS
WHEAT OR RYE	150 LB.	COVER SEED 1" TO 1 1/2" DEEP
RED TOP GRASS - Agrostis alba	1-5 LB.	COVER SEED 1/4" DEEP
SPRING OATS - Avena sativa	100 LB.	COVER SEED 1" DEEP
ANNUAL RYEGRASS - Lolium multiflorum	40 LB.	COVER SEED 1/4" DEEP

* TEMPORARY SEEDINGS TO BE ADDED TO ALL SEEDING MIXES



TYPE OF SEED - GRASSES	COMMON NAME	LBS/ACRE
Festuca arundinacea	Turf Type Tall Fescue	50
Lolium perenne	Perennial Ryegrass	43
Poa pratensis	Kentucky Bluegrass	42
GRASSES lbs PER ACRE		105

TYPE OF SEED - COVER CROP	COMMON NAME	LBS/ACRE
Avena sativa	Seed Oats	32
Lolium multiflorum	Annual Rye	6
COVER CROP lbs PER ACRE		38

SLOPE PROTECTION TABLE

OUTLET DIAMETER (INCHES)	MINIMUM DEPTH X WIDTH (CUBIC YARDS)	BRICK LINKS (FEET)
12	1 X 6 X 6	2
15	1 X 6 X 6	2
18	1.5 X 4 X 12	3
24	1.5 X 6 X 14	5
30	1.5 X 7 X 16	6
36	1.5 X 8 X 18	9
42	2 X 10 X 20	15
48	2 X 12 X 20	18
54	2 X 13.5 X 22	22
60	2 X 15 X 22	28
66	2 X 16 X 25	33
72	2 X 20 X 30	44
84	2.5 X 25 X 35	81
96	2.5 X 30 X 40	111
108	3 X 32 X 40	142

RIPRAP DETAIL AT END SECTION
 NOT TO SCALE



2014 California - ADS FLEXSTORM X-REF


California

FLEXSTORM CAUGHT IT

Standard	Inlet Type	Grate Size	Opening Size	Flow Rate (GFS)	Flow Rate (GFS)	Flow Rate (GFS)	Flow Rate (GFS)
12" x 12" precast catch basin	Concrete Box (RD)	15 x 15	12 x 12	0.9	1.0	2.5	6.5
18" x 18" precast catch basin	Concrete Box (RD)	21 x 18	18 x 18	2.1	1.5	3.9	6.5
24" x 24" precast catch basin	Concrete Box (RD)	27 x 24	24 x 24	3.4	1.9	5.0	6.5
36" x 36" precast catch basin	Concrete Box (RD)	40x17.5	36x17	2.6	2.8	5.9	6.5
48" x 48" precast catch basin	Concrete Box (RD)	40 x 24	36 x 24	5.6	2.5	6.5	6.5
60" x 60" precast catch basin	Concrete Box (RD)	40 x 36	36 x 36	7.9	4.4	10.0	6.5
72" x 72" precast catch basin	Concrete Box (RD)	62 x 48	48 x 48	13.8	5.4	12.0	6.5

Product selection for FLEXSTORM PURE Filters (Permanent Inlet Protection)

Standard	Inlet Type	Grate Equivalent	Grate Size	Flow Rate (GFS)	Flow Rate (GFS)	Flow Rate (GFS)	Flow Rate (GFS)
36" Open Throat Inlet	Open Throat (WM)	FGP-36C1	N/A	36	2.5	1.9	1.4
42" Open Throat Inlet	Open Throat (WM)	FGP-42C1	N/A	42	3.0	2.5	1.7
48" Open Throat Inlet	Open Throat (WM)	FGP-48C1	N/A	48	3.3	2.5	1.7
60" Open Throat Inlet (2 pieces)	Open Throat (WM)	FGP-60C1	N/A	60	4.2	2.5	1.7
84" Open Throat Inlet (2 pieces)	Open Throat (WM)	FGP-84C1	N/A	84	5.8	2.5	1.7
48" Open Throat with Side Wings	Open Throat (WM)	N/A	N/A	48 Winged	5.1	2.7	1.7
12" x 12" precast	Concrete Box (RD)	FGP-12E	15 x 15	0.0	1.0	0.7	2.4
18" x 18" precast	Concrete Box (RD)	FGP-18F	21 x 18	18 x 18	0.0	1.5	1.0
21" Round Opening	Round (RD)	FGP-R20F	23	21	1.5	1.3	1.1
24" Round Opening	Round (RD)	FGP-R24F	26	24	1.9	1.5	1.3
24" x 24" (shallow)	Concrete Box (RD)	FGP-24F6	27 x 24	24 x 24	3.2	1.9	0.8
36" x 36" precast	Concrete Box (RD)	FGP-3618F	40 x 18	36 x 18	3.8	2.2	1.5
36" x 36" precast	Combination	FGP-3636FGO	40 x 18	36 x 18	3.5	2.1	1.5
36" x 24" precast	Concrete Box (RD)	FGP-2436FGO	40 x 24	36 x 24	3.9	2.5	1.7
36" x 36" precast	Concrete Box (RD)	FGP-3636FGO	40 x 24	36 x 32	4.3	2.3	2.0
48" x 48" precast	Concrete Box (RD)	FGP-4836F	40 x 36	36 x 36	7.2	4.4	3.2
48" x 48" precast	Concrete Box (RD)	FGP-48F	48 x 48	48 x 48	13.0	5.4	4.2



Product selection for FLEXSTORM PURE Filters (Permanent Inlet Protection)

Standard	Inlet Type	Grate Equivalent	Grate Size	Flow Rate (GFS)	Flow Rate (GFS)	Flow Rate (GFS)	Flow Rate (GFS)
36" Open Throat Inlet	Open Throat (WM)	FGP-36C1	N/A	36	2.5	1.9	1.4
42" Open Throat Inlet	Open Throat (WM)	FGP-42C1	N/A	42	3.0	2.5	1.7
48" Open Throat Inlet	Open Throat (WM)	FGP-48C1	N/A	48	3.3	2.5	1.7
60" Open Throat Inlet (2 pieces)	Open Throat (WM)	FGP-60C1	N/A	60	4.2	2.5	1.7
84" Open Throat Inlet (2 pieces)	Open Throat (WM)	FGP-84C1	N/A	84	5.8	2.5	1.7
48" Open Throat with Side Wings	Open Throat (WM)	N/A	N/A	48 Winged	5.1	2.7	1.7
12" x 12" precast	Concrete Box (RD)	FGP-12E	15 x 15	0.0	1.0	0.7	2.4
18" x 18" precast	Concrete Box (RD)	FGP-18F	21 x 18	18 x 18	0.0	1.5	1.0
21" Round Opening	Round (RD)	FGP-R20F	23	21	1.5	1.3	1.1
24" Round Opening	Round (RD)	FGP-R24F	26	24	1.9	1.5	1.3
24" x 24" (shallow)	Concrete Box (RD)	FGP-24F6	27 x 24	24 x 24	3.2	1.9	0.8
36" x 36" precast	Concrete Box (RD)	FGP-3618F	40 x 18	36 x 18	3.8	2.2	1.5
36" x 36" precast	Combination	FGP-3636FGO	40 x 18	36 x 18	3.5	2.1	1.5
36" x 24" precast	Concrete Box (RD)	FGP-2436FGO	40 x 24	36 x 24	3.9	2.5	1.7
36" x 36" precast	Concrete Box (RD)	FGP-3636FGO	40 x 24	36 x 32	4.3	2.3	2.0
48" x 48" precast	Concrete Box (RD)	FGP-4836F	40 x 36	36 x 36	7.2	4.4	3.2
48" x 48" precast	Concrete Box (RD)	FGP-48F	48 x 48	48 x 48	13.0	5.4	4.2

FLEXSTORM INLET FILTERS DETAIL
 NOT TO SCALE



619 N Pennsylvania Street
Indianapolis, IN 46204
317.423.0690
www.y3c0.com

STORM PLAN & PROFILE

THE RIDGE ON WILLIAMS CREEK

INDIANAPOLIS

NO.	DATE	DESCRIPTION
1	09-15-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
4	11-27-23	REVISED PER CITIZENS COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-08-24	REVISED PER CITY COMMENTS





NO.	DATE	DESCRIPTION
7	02-28-24	REVISED PER CITY COMMENTS
8	05-04-24	REVISED PER CITY COMMENTS



A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
By: JN

NOTES:

1. CONTRACTOR TO FIELD VERIFY LOCATION, INVERT, AND SIZE OF ALL EXISTING UTILITIES PRIOR TO ORDERING MATERIALS FOR INSTALLATION. NOTIFY CONTRACTOR TO NOTIFY ENGINEER OF ANY DISCREPANCIES IMMEDIATELY.
2. UNLESS INDICATED OTHERWISE, FRAME AND OPEN LID STORM STRUCTURES IN PAVEMENT ALONG CURBS SHALL BE NEENAH R-3286-8V OR APPROVED EQUAL. FRAME AND CLOSED LID STORM STRUCTURES IN PAVEMENT SHALL BE NEENAH R-1712 OR APPROVED EQUAL. OPEN SPACE SHALL BE R-3421 WITH TYPE C GRATE OR APPROVED EQUAL. ALL FRAME AND GRATES SHALL CONFORM TO LOCAL MUNICIPALITY REQUIREMENTS.
3. STORM SEWER MANHOLE COVERS SHALL HAVE THE WORDS "STORM SEWER" CAST IN RECESSED LETTERS TWO (2) INCHES IN HEIGHT. SEE DETAIL ON C6.1.
4. INLET CASTINGS SHALL HAVE THE WORDS "NO DUMPING. DRAINS TO STREAM" CAST IN RAISED OR RECESSED LETTERS AT A MINIMUM OF 1" IN HEIGHT. A SYMBOL OF A FISH SHALL ALSO BE CAST WITH THE LETTERS.
5. WHERE CONNECTIONS ARE MADE TO EXISTING MANHOLES OR CURBS, THE EXISTING CURBS SHALL BE REHABILITATED OR REPLACED TO THOSE MINIMUM STANDARDS OUTLINED IN CHAPTERS 400 AND 500 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL, LATEST EDITION. THE REHABILITATION SHALL INCLUDE THE INSTALLATION OF BENCH WALLS, AS WELL AS PRESCRIBED MEASURES TO ELIMINATE THE POTENTIAL FOR MIGRATION OF BACKFILL MATERIALS INTO THE STORMWATER SYSTEM.
6. ALL PROPOSED STORM SEWER AND DRAINAGE APPURTENANCES SHALL BE IN CONFORMANCE WITH CHAPTERS 400 AND 500 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL, LATEST EDITION. DISCREPANCIES BETWEEN THE PLANS AND THE MANUAL SHALL NOT ALLEVIATE SET FORTH IN THE MANUAL.



SCALE:
1" = 20' (HORIZ)
1" = 5' (VERT)



619 N Pennsylvania Street
 Indianapolis, IN 46204
 317.423.0590
 www.v3co.com

STORM PLAN & PROFILE




THE RIDGE ON WILLIAMS CREEK

INDIANAPOLIS

NO.	DATE	DESCRIPTION
1	09-16-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY AND CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
4	11-27-23	REVISED PER CITY AND CITIZENS COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

- NOTES:
- CONTRACTOR TO FIELD VERIFY LOCATION, INVERT, AND SIZE OF EXISTING UTILITIES PRIOR TO ORDERING MATERIALS OR BEGINNING UTILITY WORK. CONTRACTOR TO NOTIFY ENGINEER OF ANY DISCREPANCIES IMMEDIATELY.
 - UNLESS INDICATED OTHERWISE, FRAME AND OPEN LID STORM STRUCTURES IN PAVEMENT SHALL BE NEENAH R-2386-RV OR APPROVED EQUAL. FRAME AND CLOSED LID STORM STRUCTURES IN PAVEMENT SHALL BE NEENAH R-1712 OR APPROVED EQUAL. FRAME AND OPEN LID STORM STRUCTURES IN OPEN SPACE SHALL BE R-3472 WITH TYPE C GRATE OR APPROVED EQUAL. ALL FRAME AND GRATES SHALL CONFORM TO LOCAL MUNICIPALITY REQUIREMENTS.
 - STORM SEWER MANHOLE COVERS SHALL HAVE THE WORDS "STORM SEWER" CAST IN RECESSED LETTERS TWO (2) INCHES IN HEIGHT. SEE DETAIL ON C6.1.
 - INLET CASTINGS SHALL HAVE THE WORDS "NO DUMPING, DRAINS TO STREAM" CAST IN RAISED OR RECESSED LETTERS AT A MINIMUM OF 1" IN HEIGHT. A SYMBOL OF A HSB SHALL ALSO BE CAST WITH THE LETTERS.
 - WHERE CONNECTIONS ARE MADE TO EXISTING MANHOLES OR INLET STRUCTURES, THOSE STRUCTURES SHALL BE REHABILITATED OR REPLACED TO THOSE MINIMUM STANDARDS OUTLINED IN CHAPTERS 400 AND 500 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS. THE LATEST EDITION, THE REHABILITATION WORK SHALL INCLUDE THE INSTALLATION OF REINFORCED CONCRETE MANHOLES AS WELL AS PRESCRIBED MATERIALS TO ELIMINATE THE POTENTIAL FOR MIGRATION OF BACKFILL MATERIALS INTO THE STORMWATER SYSTEM.
 - ALL PROPOSED STORM SEWER AND DRAINAGE WITH CHAPTERS 400 AND 500 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL AND THE MANUAL SHALL NOT ALLEVIATE BETWEEN THE PLANS AND THE MANUAL. ALL REQUIREMENTS AS SET FORTH IN THE MANUAL.

MATCHLINE - SEE SHEET C5.2



LEGEND
 GRANULAR BACKFILL

A202400023641
03/28/2024 10:58 AM
 FAITH KIMBROUGH
 MARION COUNTY IN RECORDER
 FEE: \$ 140.00
 PAGES: 60
 By: JN



SCALE:
 1"=20' (HORIZ)
 1"=2' (VERT)





619 N Pennsylvania Street
 Indianapolis, IN 46204
 317.423.0680
 www.v3co.com


INDIANAPOLIS
THE RIDGE ON WILLIAMS CREEK
STORM PLAN & PROFILE

NO.	DATE	DESCRIPTION
1	09-15-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY AND CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
4	11-27-23	REVISED PER CITY AND CITIZENS COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS


PROJECT NO.: 220851 S04
 PROJECT MANAGER: JOR
 DESIGNED BY: MRY
 DRAWN BY: MRY

ORIGINAL ISSUE DATE: 07-07-2023

- NOTES:**
- CONTRACTOR TO FIELD VERIFY LOCATION, INVERT, AND SIZE OF EXISTING UTILITIES PRIOR TO ORDERING MATERIALS OR BEGINNING UTILITY WORK. CONTRACTOR TO NOTIFY ENGINEER OF ANY DISCREPANCIES IMMEDIATELY.
 - UNLESS INDICATED OTHERWISE, FRAME AND OPEN LID STORM STRUCTURES IN PAVEMENT ALONG CURBS SHALL BE NEENAH R-3288-40V OR APPROVED EQUAL. FRAME AND CLOSED LID STORM STRUCTURES IN OPEN SPACE SHALL BE R-3472 WITH TYPE C GRATE OR APPROVED EQUAL. ALL FRAME AND GRATES SHALL CONFORM TO LOCAL MUNICIPALITY REQUIREMENTS.
 - STORM SEWER MANHOLE COVERS SHALL HAVE THE WORDS "STORM SEWER" CAST IN RECESSED LETTERS TWO (2) INCHES IN HEIGHT. SEE DETAIL ON C6.1.
 - INLET CASTINGS SHALL HAVE THE WORDS "NO DUMPING. DRAINS TO STREAM" CAST IN RAISED OR RECESSED LETTERS AT A MINIMUM OF 1" IN HEIGHT. A SYMBOL OF A FISH SHALL ALSO BE CAST WITH THE LETTERS.
 - WHERE CONNECTIONS ARE MADE TO EXISTING MANHOLES OR INLET STRUCTURES, THOSE STRUCTURES SHALL BE REHABILITATED OR REPLACED TO THOSE MINIMUM STANDARDS OUTLINED IN CHAPTERS 400 AND 500 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL, LATEST EDITION. THE REHABILITATION SHALL INCLUDE THE INSTALLATION OF BENCH WALLS, AS WELL AS PREScribed BACKFILL MATERIALS INTO THE STORMWATER SYSTEM.
 - ALL PROPOSED STORM SEWER AND DRAINAGE APPURTENANCES SHALL BE IN CONFORMANCE WITH CHAPTERS 400 AND 500 OF THE CITY OF INDIANAPOLIS STORMWATER SPECIFICATIONS MANUAL, LATEST EDITION. DISCREPANCIES BETWEEN THE PLANS AND THE MANUAL SHALL NOT ALLEVIATE CONTRACTOR'S RESPONSIBILITY FOR ADHERING TO THE REQUIREMENTS AS SET FORTH IN THE MANUAL.



STATION	PIPE TYPE	LENGTH	SLOPE	INVERT ELEVATION (IE)	MANHOLE INVERT ELEVATION (MH IE)	MANHOLE RIM ELEVATION (MH RIM)
3+00	4" MH (OPEN) R-3472 FRAME	70 LF	3.41%	805.88 (S)	809.30 (N)	805.99 (N)
3+00	4" MH (OPEN) R-3472 FRAME	70 LF	3.41%	803.25 (S)	807.00 (N)	803.50 (N)
4+00	4" MH (CLOSED) R-1712 FRAME	104 LF	0.61%	802.02 (SE)	806.16 (NW)	802.02 (SE)
5+00	4" MH (CLOSED) R-1712 FRAME	71 LF	0.47%	802.19 (S)	808.38 (NW)	802.19 (S)
6+00	4" MH (CLOSED) R-1712 FRAME	43 LF	0.44%	802.00 (N)	808.38 (NW)	802.00 (N)



A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
 FEE: \$ 140.00
 PAGES: 60
 BY: JN






SCALE:
1"=20' (HORIZ)
1"=2' (VERT)

3+00 3+15


2+00

1+00

0+00




A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
By: JN



NO.	DATE	DESCRIPTION
1	09-18-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY AND CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
4	11-27-23	REVISED PER CITY AND CITIZENS COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

NOTES:

- CONTRACTOR TO FIELD VERIFY LOCATION, INVERT, AND SIZE OF ALL EXISTING UTILITIES PRIOR TO ORDERING MATERIALS OR BEGINNING UTILITY WORK. CONTRACTOR TO NOTIFY ENGINEER OF ANY DISCREPANCIES IMMEDIATELY.
- UNLESS INDICATED OTHERWISE, FRAME AND OPEN LID STORM STRUCTURES IN PAVEMENT SHALL BE NEENAH R-1712 OR APPROVED EQUAL. FRAME AND OPEN LID STORM STRUCTURES IN PAVEMENT SHALL BE NEENAH R-1712 OR APPROVED EQUAL. FRAME AND GRATES SHALL CONFORM TO LOCAL MUNICIPALITY REQUIREMENTS.
- STORM SEWER MANHOLE COVERS SHALL HAVE THE WORDS "STORM SEWER" CAST IN RECESSED LETTERS TWO (2) INCHES IN HEIGHT. SEE DETAIL ON C6.1.
- INLET CASTINGS SHALL HAVE THE WORDS "NO DUMPING. DRAINAGE SEWER. CAST IN RAISED OR RECESSED LETTERS AT A MINIMUM OF 1" IN HEIGHT. SYMBOL OF A FISH SHALL ALSO BE CAST WITH THE LETTERS.
- WHERE CONNECTIONS ARE MADE TO EXISTING MANHOLES OR INLET STRUCTURES, THOSE STRUCTURES SHALL BE REHABILITATED OR REPLACED TO THOSE MINIMUM STANDARDS NOTED IN CHAPTERS 400 AND 500 OF THE CITY OF INDIANAPOLIS REHABILITATION SPECIFICATIONS MANUAL, LATEST EDITION. THE REHABILITATION SHALL, AS WELL AS PRESCRIBED MEASURES TO ELIMINATE THE POTENTIAL FOR MIGRATION OF BACKFILL MATERIALS INTO THE STORMWATER SYSTEM.
- ALL PROPOSED STORM SEWER AND DRAINAGE APPLIANCE SHALL BE IN CONFORMANCE WITH CHAPTERS 400 AND 500 OF THE CITY OF INDIANAPOLIS REHABILITATION SPECIFICATIONS MANUAL, LATEST EDITION. THE CONTRACTOR SHALL VERIFY THE ACCURACY OF THE DATA BETWEEN THE PLANS AND THE MANUAL. THE MANUAL SHALL NOT ALLEVIATE THE CONTRACTOR'S RESPONSIBILITIES TO SET FORTH IN THE MANUAL.



STORM PLAN & PROFILE
THE RIDGE ON WILLIAMS CREEK
INDIANAPOLIS

PROJECT NO.: 220851 S04
DESIGNED BY: MVR
DRAWN BY: MVR
PROJECT MANAGER: JOR
INDIANAPOLIS
619 N Pennsylvania Street
Indianapolis, IN 46204
317.423.0690
www.v3co.com


DRAWING NO. **C5.4**

A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
BY: JN

Indiana 811
 Know what's below. Call before you dig.
 STATE OF INDIANA
 DEPARTMENT OF TRANSPORTATION
 DIVISION OF HIGHWAYS


STORM SEWER TABLE

PIPE NAME	PIPE MATERIAL & SIZE	LENGTH	SLOPE	BEARING
FES 3-1 - ST 3-1	12" RCP	21'	0.00%	S41°41'55.13"W
FES 4-1 - FES 4-2	12" RCP	89'	1.62%	S79°36'44.48"W
FES 4-3 - FES 4-4	12" RCP	76'	1.45%	S76°27'56.66"E
ST 1-1 - ST 1-1B	15" RCP	104'	0.61%	S08°27'57.39"E
ST 1-1A - FES 1-1	15" RCP	43'	0.44%	S15°04'21.86"E
ST 1-1B - ST 1-1A	15" RCP	71'	0.47%	S61°54'36.55"E
ST 1-2 - ST 1-1	12" RCP	70'	3.41%	S16°48'08.54"E
ST 1-3 - ST 1-2	12" RCP	197'	1.25%	S02°44'23.67"E
ST 1-4 - ST 1-3	12" RCP	110'	0.86%	S11°53'05.13"W
ST 2-1 - FES 2-1	12" RCP	246'	0.63%	S08°57'31.81"E
ST 3-1 - FES 3-2	15" HDPE	8'	0.29%	S12°30'31.33"W
ST 3-1A - FES 3-2	15" HDPE	35'	0.16%	S12°19'13.11"W
ST 5-1 - FES 5-1	12" RCP	26'	6.67%	N80°21'36.05"W
ST 5-2 - ST 5-1	12" RCP	44'	5.82%	N11°38'19.64"W
ST 5-3 - ST 5-2	12" RCP	65'	2.00%	N57°38'00.28"W
ST 5-4 - ST 5-3	12" RCP	76'	0.50%	N00°50'13.17"W
ST 5-5 - ST 5-4	12" RCP	62'	0.50%	N16°20'16.56"W



STORM STRUCTURE TABLE

STRUCTURE	RIM	PIPES IN	INVERT IN	PIPES OUT	INVERT OUT	PIPE LENGTH OUT	DOWNSTREAM STRUCTURE	STRUCTURE TYPE	LOCATION
FES 1-1	RIM: N/A	15" RCP	802.00 (15' N)					15" FES	1703372.40, 185753.22
FES 2-1	RIM: N/A	12" RCP	819.76 (12' N)					12" FES	1704168.80, 185650.64
FES 3-1	RIM: N/A			12" RCP	789.10 (12' SW)	21 LF	ST 3-1	12" FES	1703097.51, 185600.26
FES 3-2	RIM: N/A	15" HDPE	789.02 (15' N)					15" AGRICULTURAL FLAP GATE SEE C6.4 FOR DETAIL	1703039.62, 185780.18
FES 4-1	RIM: N/A			12" RCP	781.45 (12' W)	89 LF	FES 4-2	12" FES	1703324.46, 186533.03
FES 4-2	RIM: N/A	12" RCP	780.00 (12' E)					12" FES	1703306.37, 186445.82
FES 4-3	RIM: N/A			12" RCP	780.00 (12' E)	76 LF	FES 4-4	12" FES	1703089.80, 186581.29
FES 4-4	RIM: N/A	12" RCP	778.90 (12' W)					12" FES	1703072.07, 186654.86
FES 5-1	RIM: 802.84	12" RCP	803.00 (12' E)					12" FES	1703488.34, 185500.00
ST 1-1	RIM: 807.00	12" RCP	803.50 (12' N)	15" RCP	803.25 (15' S)	104 LF	ST 1-1B	4" MH (Open) R-3472 FRAME	1703649.84, 185664.23
ST 1-1A	RIM: 808.38	15" RCP	802.19 (15' NW)	15" RCP	802.19 (15' S)	43 LF	FES 1-1	4" MH (Closed) R-1712 FRAME	1703414.07, 185741.99
ST 1-1B	RIM: 808.15	15" RCP	802.62 (15' N)	15" RCP	802.52 (15' SE)	71 LF	ST 1-1A	4" MH (Closed) R-1712 FRAME	1703447.44, 185679.47
ST 1-2	RIM: 809.30	12" RCP	805.99 (12' N)	12" RCP	805.89 (12' S)	70 LF	ST 1-1	4" MH (Open) R-3472 FRAME	1703616.93, 185643.95
ST 1-3	RIM: 816.04	12" RCP	808.55 (12' N)	12" RCP	808.45 (12' S)	197 LF	ST 1-2	4" MH (Closed) R-1712 FRAME	1703814.07, 185634.52
ST 1-4	RIM: 811.60			12" RCP	809.50 (12' S)	110 LF	ST 1-3	2" Inlet R-3472 FRAME	1703821.63, 185657.15
ST 2-1	RIM: 824.81			12" RCP	821.31 (12' S)	246 LF	FES 2-1	2" Curb Inlet R-3288-8V FRAME	1704411.93, 185612.31
ST 3-1	RIM: 794.75	12" RCP	789.10 (12' NE)	15" RCP	789.10 (15' S)	8 LF	ST 3-1A	5" MH (Closed) RESTRICTOR STRUCTURE SEE DETAIL ON C6.1	1703082.03, 185789.47
ST 3-1A	RIM: 794.59	15" RCP	789.08 (15' N)	15" HDPE	789.08 (15' S)	35 LF	FES 3-2	5" MH (Closed) CONTECH CASCADE CS-5 WATER QUALITY STRUCTURE SEE DETAIL ON C6.2	1703074.06, 185787.70
ST 5-1	RIM: 810.34	12" RCP	804.74 (12' S)	12" RCP	804.74 (12' W)	26 LF	FES 5-1	4" MH (Closed) R-1712 FRAME	1703484.47, 185925.71
ST 5-2	RIM: 811.45	12" RCP	807.32 (12' SE)	12" RCP	807.32 (12' N)	44 LF	ST 5-1	4" MH (Open) R-3472 FRAME	1703441.07, 185934.65
ST 5-3	RIM: 816.30	12" RCP	809.01 (12' S)	12" RCP	809.01 (12' NW)	85 LF	ST 5-2	4" MH (Open) R-3472 FRAME	1703395.81, 186006.06
ST 5-4	RIM: 815.08	12" RCP	809.39 (12' S)	12" RCP	809.39 (12' N)	76 LF	ST 5-3	4" MH (Open) R-3472 FRAME	1703319.83, 186007.17
ST 5-5	RIM: 813.70			12" RCP	809.70 (12' N)	62 LF	ST 5-4	2" Inlet R-3472 FRAME	1703259.96, 186024.73



REVISIONS

NO.	DATE	DESCRIPTION
1	09-15-23	REVISED PER CITY AND CITIZENS COMMENTS
2	10-18-23	REVISED PER CITY AND CITIZENS COMMENTS
3	11-15-23	REVISED PER CITY AND CITIZENS COMMENTS
4	11-27-23	REVISED PER CITY AND CITIZENS COMMENTS
5	01-08-24	REVISED PER CITY COMMENTS
6	02-09-24	REVISED PER CITY COMMENTS

INDIANAPOLIS
THE RIDGE ON WILLIAMS CREEK
STORM STRUCTURE TABLE

INDIANA


PROJECT NO: 220851 S04
 PROJECT MANAGER: JOR
 DESIGNED BY: MRV
 DRAWN BY: MRV

619 N Pennsylvania Street
 Indianapolis, IN 46204
 317.423.0690
 www.v3co.com


DRAWING NO. **C5.5**

SCALE:
 1"=20' (HORIZ)
 1"=2' (VERT)

A202400023641
03/28/2024 10:58 AM
FAITH KIMBROUGH
MARION COUNTY IN RECORDER
FEE: \$ 140.00
PAGES: 60
BY: JN




SCALE
 1"=20'




SCALE:
 1"=20' (HORIZ)
 1"=5' (VERT)

DETENTION BASIN AND BMP PLAN AND CROSS SECTIONS



01 TYPICAL DETENTION BASIN CROSS SECTION
 NOT TO SCALE

DETENTION BASIN CROSS-SECTION NOTES:
 1. SLOPES, TOB, DIMENSIONS, ETC. VARY. REFER TO GRADING PLAN AND UTILITY PLAN FOR ADDITIONAL DETAIL.



EMERGENCY OVERFLOW WEIR GEOMETRY CALCULATION

OVERFLOW WEIR MUST CONVEY 1.25 TIMES THE 100-YEAR RELEASE RATE.

Q = ANTICIPATED 100 YEAR RELEASE RATE

DETENTION BASIN

$Q = 19.73 \times 1.25 = 24.66 \text{ CFS}$

$L = 30 \text{ FT}$


$H_{M1.5} = 0.125$

3.367 L


$H = 0.25'$

SPILLWAY ELEVATION = 793.50

HIGH WATER ELEVATION = 793.75



EMERGENCY SPILLWAY DETAIL



CS-5 CASCADE SEPARATOR STANDARD DETAIL

CONTECH
 ENGINEERING SOLUTIONS LLC
 1111 W. 12TH AVENUE, SUITE 200
 DENVER, CO 80202
 TEL: 303.733.7300
 WWW.CONTECHENGINEERING.COM



619 N Pennsylvania Street
 Indianapolis, IN 46204
 317.423.6990
 WWW.V3CO.COM